**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Patvin Engineering Private Limited**
Patvin House, W-193, TTC Industrial Area,
MIDC Khairane, Navi Mumbai - 400 709

**Date : 28.09.2020**
Quote NO : SQT.20.21.2668 R
**Kind Attn : Mr. Ganesh Thopate**
Email Id : proposals@patvin.co.in
Contact No: **8108272794**

**Subject : Quotation for Fire rated Sliding Door at Maruti Suzuki Plant**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2, 3, 4 |
| C. | General Conditions | 5 |
| D. | Terms & Condtions | 5 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | Fire Rated Sliding Door | 1880 | 2200 | 1 | 120,000 | 120,000 | 20,000 | 20,000 |
| | | | | **Total** | | **120,000** | | **20,000** |
| | P&F Charges | | | 3% | | **3,600** | | |
| | **Total Without Taxes** | | | | | **123,600** | | **20,000** |
| | GST Extra @ 18% | | | 18% | | 22,248 | | 3,600 |
| | **Total With Taxes** | | | | | **145,848** | | **23,600** |
| | **Total Supply + Installation with Taxes** | | | | | | | **169,448** |
| 2 | Transportation Charges | | | | | **In Client Scope** | | |
| 3 | Unloading Charges @ Site | | | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Fire Rated Sliding Door**

| Sr. No | Description | Specification |
|---|---|---|
| 1 | Door type | Fire Resistant Door Fusible link (Rated for 68 deg. C based Auto Sliding type (2 hours fire rated) |
| 2 | Door Diemension size | 2080mm (W) x 2300mm (H) |
| | | As per the norms an overlapping of 100 mm in height and 200 mm in width is considered while calculating the sizes of the doors and is mandatory to restrict fire from escaping from the gaps between the wall and the shutters. This door is always kept into open position and at the time of fire break, fusible link melts which allows the counter weight hung to the wire rope to pull the panel automatically close and to prevent fire from spreading further. Standard accessories are included in the supply. |
| 3 | Accessories Included | Fusible link, wire rope, guide rail, counter weight, pulleys as per BS 476, Part 20 & 22 and standard accessories included |
| 4 | Glass | Not Considered |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex works Pune

**Delivery** : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd