NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

CONTINENTAL ELECTRONICS
Plot No. 177 / 4, Phase-1, B/h.
Ingersall Rand Bus Stop
Naroda G.I.D.C., Ahmedabad - 382330

Date : 12.11.2019
Quote NO : SQT/19-20/2235
Kind Attn : Mr. Manish Wagh
Email Id : sales.celtronics@gmail.com
Contact No: 98980 85837

Subject : Quotation for Sectional Door. (Project -CONTINENTAL ELECTRONICS, Ahmedabad) .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Sectional Door**	6500	4000	2	456,000	912,000	20,000	40,000
				Total		**912,000**		**40,000**
2			P&F Charges	3%		27,360		
			Total Without Taxes			939,360		40,000
			GST Extra @ 18%	18%		169,084.80		7,200
			Total With Taxes			**1,108,445**		**47,200**
3			Transportation Charges			In Client Scope		
4			Unloading Charges @ Site			In Client Scope		

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr .No.	Specification	Sectional Door -Crawford - NIHVA Assaabloy	
1	**Door type**	1042P	
2	**Clear Opening dimension**	(W)6500 x (H) 4000 mm	
3	**Interlocking**	Included	
4	**Type of Mounting**	High Lift	
5	**Door produced Based on which certificatio**	Doors produced according to ISO 9000 or ISO 14000 certified	
6	**Opening/Closing Speed**	0.25 m/s	
7	**Door Material**	GI Steel with PUF inside	
8	**Panel Thickness**	42mm	
9	**Panel colour**	RAL 9002 Powder coated	
10	**External surface of the panel**	diamond grid design with a glossy finish at the section joints.	
11	**inside surface of the panel**	Monolithic surface on the inside of the door	
12	**Broken cold bridge**	Section joints with broken cold bridges	
13	**Door sealent**	All door sealants made of EPDM rubber.	
14	**All Panel height**	All panels should be 545mm high	
15	**Panel Inside insulation metrial**	Insulation material to be CFC free polyuretane foam.	
16	**Panel Flame Retardent standrad**	Flame retardant polyurethane foam according DIN4102-class B2.	
17	**Steel component Material**	All steel components to be electro galvanized	
18	**Hinge Material**	Glass fibre reinforced Polyamide	
19	**Panel Thickness**	42 mm	
20	**Spring Material surface finish**	Powder coated	
21	**Water Penetration**	EN 12425	class 3
22	**Air Permealibity**	EN12426	class 2
23	**Wind Load**	EN21424	class 3
24	**Thermal Transittance**	EN 12428 1.10W /m2K	
25	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber	
26	**Door saftey device 1**	Doors equiped with spring break device	
27	**Door saftey device 2**	Door equiped with pneumatic safety edge	
28	**Door saftey 3**	Having hinges flush with the inside door surface is a safety feature that eliminates the risk of things or people getting caught by parts protuding from a moving door	
29	**Incase of Power failuer**	One can operate the Door manually	
30	**Operator power conumption**	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W	
31	**Drive Unit & Mounting Type**	Single phase 230V direct drive on shaft	
32	**Emergency Operation**	by Disengagement rope manual	
33	**Operating Switch**	Up/Down Keypad + stopbutton	
34	**Environmental Green Product Declaration Certification**	as per ISO 14025 and EN 15804	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr.Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd