NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Suroj Buildcon Pvt Ltd.
Bungalow No. 3, Liberty Society Phase-I,
North Main Road,
Koregaon Park, Pune 411 001, Maharashtra, India.

Date : 12.06.2020
Quote NO : SQT/19-20/2607
Kind Attn : Mr.Prashant Patil
Email Id : pspatil@suroj.in
Contact No: 7447459207

Subject : Quotation for Fire Rated Rolling Shutter, Sectional Door and Sectional Door. (Project - M/s. Kimberly Clark, Sanaswadi, Pune)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Fire Rated Rolling Shutter**	3000	3000	3	239,000	717,000	20,000	60,000
2	**Fire Rated Rolling Shutter**	3000	4000	2	287,000	574,000	20,000	40,000
3	**Fire Rated Rolling Shutter**	3000	5000	3	302,000	906,000	20,000	60,000
4	**Sectional Door**	3000	3000	3	258,000	774,000	20,000	60,000
5	**High Speed Door**	3000	3000	3	542,000	1,626,000	20,000	60,000
				Total		**4,597,000**		**280,000**
6	P&F Charges			3%		137,910		
	Total Without Taxes					**4,734,910**		**280,000**
	GST Extra @ 18%			18%		852,283.80		50,400
	Total With Taxes					**5,587,194**		**330,400**
7	Transportation Charges					In Client Scope		
8	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification





2 Hrs. Fire Rated Rolling Shutters

- **Shutter Slats: Zinc coated steel solid slats**
- **Slat Thickness: 1.0mm thick**
- **Shutter Guide: Galvanize Steel, 3mm thick**
- **Operated by: Motor with one unit push button switch & manual override**

Design:
Roll formed from 1st grade BHP Zincalume steel curve slat curtain

Guide Rail:
Fabricated from hot-dipped galvanized steel of 3.0mm with one-piece design surface mounted type

Bottom Bar:
Assembled of 2 pieces of 38x38x3mm galvanized steel angle bolted 800mm pitch with galvanized bolts and nuts or 2 pieces of 40x40x6mm steel flat bar.

Shutter Enclosure Box:
Fabricated from heavy duty 7.0mm steel plate for both ends and supports with steel frame with very well black primer one coat. Box covers shall be of 0.8mm steel sheets with BHP zincalume finishing.

Motor Drive Unit:
- **Power Source:**
  230v 50Hz 1 phase
- **Manual Chain Override**
- **One-unit push button switch**
- **Gravity drop level**
- **Fire Shutter will autoclose via 71 Degree Celcius Thermal Fusible Link**
- **Auto close by relay switch after receive of 24vdc fire signal**

Standard RAL colors:
- **RAL 1015**
- **RAL 7025**
- **RAL 9010**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification



Sr .No.	Specification	Sectional - Crawford - NIHVA Assaabloy
1	**Door type**	1042P
3	**Opening Direction**	90 Degree
5	**Door produced Based on which certificatio**	Doors produced according to ISO 9000 or ISO 14000 certified processes
6	**Opening/Closing Speed**	0.25 m/s
7	**Door Material**	GI Steel with PUF inside
8	**Panel Thickness**	42mm
9	**Panel colour**	RAL 9002 Powder coated
10	**External surface of the panel**	diamond grid design with a glossy finish at the section joints.
11	**inside surface of the panel**	Monolithic surface on the inside of the door
12	**Broken cold bridge**	Section joints with broken cold bridges

Technical Specification



Sr .No.	Specification	HS9020G
1	**Structure**	Galvanized steel
2	**Colours**	8 standard colors - white, yellow, green, orange, red, gray, black, blue
3	**Safety**	• Photocells in side columns • Flexible soft bottom edge including wireless edge activator • Break-away and self-repair function
4	**Operation**	Operator + control unit
5	**Operating speed**	Opening: up to 1,2 m/s (optional 2,0 m/s) ; Closing: 0,5 m/s
6	**Wind load resistance**	Class 1 (300 Pa (N/m²)) maximum wind load while closing 50 N/m²
7	**Air permeability**	Class 1 (24 m³/m²/h at 50 Pa)
8	**Water penetration**	Class 2 (50 Pa (N/m²))
9	**Thermal transmittance**	6,02 W/(m²K)
10	**Lifetime expectations**	1.000.000 cycles
11	**Temperature working range**	5 °C to +40 °C
12	**Vision window**	Horizontal one row of height 400 mm at eye level

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 11 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Bahvin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd