Sales Quotation

Quotation No - SQT/19-20/1791R2 **Date : 29.07.19**

Metro Lab Engineering Private Limited,Chikhali

Kind Attn: Mr.Tushar P. Gholap
Email: tushar.gholap@metrolab.engineering
Contact No: 9665467137

Project Name & Location: Metro Lab Engineering Pvt. Ltd and Chikhali

Subject : Quotation for Scissor Lift

Dear Sir
Thank you for the opportunity and trust shown on "NIHVA", your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; Please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Total Amount INR
A	**FLOOR MOUNTED SCISSOR LIFT** **Supply**				
1	Capacity : 1300 kgs Platform size : 3000L x 1000W Shut ht : 500 mm Max ht : 1700 mm Lift ht : 1200 mm Power pack : 3HP, 3PH Safety railing : 900 mm height both length side. Color : as per required. Safety bellows from all side. Hooter provide on control panel. Hose burst valve provide for safety. Standard bought part of scissor lift details. 1.Power pack – a.Pump b.Motor- Siemens/Belco c.Oil level Indicator-Hydroline d.Manifold-Puppet Valve-Hydrofit 2.Cylinder- NIHVA make 3.Control Panel: Eldon 4.Flexible Hose- Parker/Equivalent 5.Limit Switches-Ideal/Technik 6.Cable-Polycab 7.Oil-Grade 68(Hydraulic) 8.Paint-Glossy	4	Nos	425,000	1,700,000
	Total				1,700,000

NOTE: Hydraulic Oil & installation charges will confirm you in two days time.

GST Pune	27AAECN0437H1ZM

Total	**1,700,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1. **Price** : Ex Works Pune
2. **P & F Charges** : Export Packing at your end
3. **Freight Notes** : Extra As applicable
4. **Delivery** : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
5. **Payment** : 40% Advance along with Confirmed Purchase Order , 50% before dispatch, 10% after installation.
6. **Insurance** : Extra As applicable
7. **Tax** : GST Extra @ actual
8. **Validity** : Validity of Offer is 15 days from the date of quotation
9. **Warranty** : 2 Yrs from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat** on 7410169333 . For any further Clarification /Information in this Concern.

With Best Regards

Varsha
8551091333
For NIHVA Technologies Pvt Ltd