Supply & Installtion of Telescopic belt conveyor		Supplier Name	NIHVA Technologies
Technical Specifcations - Telescopic Belt conveyor		Contact No	Vijay 8551093333
DOC REF	STD-LE-BQ-R0-RFP-TELESCOPIC BELT CONVEYOR	Address	Pune maharashtra
DRG NO	LT000025	Manufacturer name	NIHVA Technologies
LOGIC DOC	NA		

EHS CHECK POINTS- SUGGESTED BY CLIENT

S.no	Telescopic belt Conveyor	Supplier Remark
1	Pop out rollers shall be provisioned between the belt & roller conveyors to avoid the trap points	Ok
2	All control switches of the TBC should design basis on the "Hold to Run effect"	Ok but steel need to clarify by customer
3	Sping-loaded extension bar shall be fitted in front of the boom to prevent the person get trapped in-between telescopic belt conveyor & truck.	Ok
4	Bottom guards shall be designed & installed for the belt conveyor.	Maximum possible bottom guards will provide
5	Brush strips shall be installed between each moving stage of the conveyor to prevent debris / hand being drawn into the machine during retraction.	Gap between two booms are not more than 15-20 mm , so brush may not be required.
6	Boom end lights shall be considered in the design	Ok Tube light or Focus light
7	Fixed guards shall be mounted for all sprockets, chains rollers, belts and other moving parts.	For exposed sprocket and moving parts we will provide gaurds.
S.no	**General Points**	
1	LOTO provision shall be ensured on the isolation switches. Energy isolation switch shall be provisioned for module wise to ensure local isolation.	Ok , For each motor you need at near to motor or in control panel only please confirm
2	Double earthing for the machine & equipments, electrical drives, control panel & body of the machine shall be ensured	Ok
3	All electrical panels should be provisioned with rubber mat / earth protection device / arc flash boundary / warning signs etc.	Ok
4	Energy isolation placard/ safety device mapping etc. shall be part of the vendor scope.	Ok
5	Location of the machine & equipment should not block access to any fire protection system / electrical panel/ emergency exits / aisle etc.	Ok
6	Lifting plan / method statement / risk assessment shall be shared with EHS for perusal	Ok after PO approval we will provide
7	Machinery & Equipments and its components shall be free from sharp edges.	Ok
8	Lifting position from the conveyors shall not be more than1.2m	Ok as per design we will provide
9	Design risk assessment as per ISO 12100, OEM Manual & inventory of safety devices shall be shared by Adverb team.	Ok after PO approval we will provide
10	E-stop shall be provisioned at every 15 m intervals at both sides of the tote conveyor system. Category 0 & 1 only to be used for emergency stop as per the conveyor application.	Either 0 or 1 category can be used
11	Entire conveyor system shall be designed on fail safe architecture and all safety devices must meet performance level d & category 3 as per Functional safety requirements.	Ok
12	HMI / SCADA with necessary backup history shall be provisioned.	**Only HMI along with control panel will be provided**
13	Anti-fatigue floor mat shall be ensured.	NA
14	C02 & DCP type FEs 1 nos/panel shall be considered	Ok
15	LOTO accessories in required nos shall be included.	Ok