NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Qualites Infrastrukrure
Survey No. 964B+965, Office No. 302, 3rd Floor,
Nilay Apartment Atreya Society
Ghokale Nagar Road, New Deep Bungalow Chowk, Shivaji nagar
Pune-16

Date : 09.10.2020
Quote NO : SQT.20-21.2749
Kind Attn : Anwar Jikare
Email Id : azikare@qualitesinfra.com
Contact No: 8308257089

Subject : Quotation for Motorised Single Leaf Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorised Single Leaf Sliding Gate	12000	1500	2	563,000	1,126,000	20,000	40,000
2	Motorised Single Leaf Sliding Gate	10000	1500	1	500,000	500,000	20,000	20,000
3	Wicket Gate	1200	1200	3	30,000	90,000	10,000	30,000
4	Wicket Gate	1000	1350	2	25,000	50,000	10,000	20,000
5	Boom Barrier - 4 mtr		4000	6	120,000	720,000	20,000	120,000
6	Boom Barrier - 5 mtr		5000	6	120,000	720,000	20,000	120,000
				Total		**3,206,000**		**350,000**
2	P&F Charges			3%		96,180		
	Total Without Taxes					3,302,180		350,000
	GST Extra @ 18%			18%		594,392.40		63,000
	Total With Taxes					**3,896,572**		**413,000**
3	Transportation Charges					In Client Scope		
4	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA make – Motorized Sliding Gate	
Door type	**Single Leaf Sliding Gate**
Opening Direction	Horizontal - from left to right or reverse
Mounting Location area	Inside area
Design Pattern	Standard Tubular Design Pattern
Outer Tube	100 X 50 X 4 mm THK SQ. TUBE
For Post	100 X 50 X 4 mm THK SQ. TUBE
Inner Vertical Flat	50 X 10 mm FLAT
Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
El motor make	BFT – Italy (100% imported)
Emergency Operation	Manual after turn the switch
Operating Switch	Push Button from inside
Safety	Photocells, Flashing Light
Metal Rack	zinc plated metal rack

Boom Barrier

Description	Specifications
Size	4 meter / 6 meter
Make	BFT
Opening time	3S
Motor Power Supply	24V
Type of limit Switch	Electronic
Safety	Photocell sensor, Flashing Light With Buzzer
Control Unit	Remote Control

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd