CONSTRUCTION DIVISION

CD\127\21-22\NI-2109\048
07th FEBRUARY 2022

****
* APPROVED BY MATERIAL *
* PRICING COMMITTEE VIDE *
* APPROVAL NO – SER/APP *
*21-22/9-43 *
* DT. 29.01.2022 *
****

To,
NIHVA Technologies Pvt. Ltd.
187, G-Block, Thermax chowk, MIDC
Chinchwad, Pune – 411019.
Phone:+91 (0) 2066304033

SUBJECT: Annual rate contract (ARC) for Supply, Installation, Testing & Commissioning of Double skinned Galvanised shutters with PUF insulation for temperature control(23 degree +/- 3 degree) having Motorisation system and Automated Rapid roll up shutters and automated fully glazed sliding doors of various sizes at TATA Motors Ltd. CVBU Pune for a period from 01-Jan-2022 to 31-Dec-2023.

Dear Sir/Madam,
We have received approval for your proposal of annual rate contract of various types of shutters and herewith we are entering in to an agreement of the ARC with the rates and terms and conditions as mentioned below and with rates and specifications as per annexure.

a) Job Completion as and when required up to: - **31\12\2023.**

b) Payments Terms: -

1) Supply- Payment on 45 days of supply. 5% retention for one year.
2) Installation-Payment on 45 days of bill submission and verification by construction department. 5% retention for one year.
   The payment terms agreed during negotiation will be valid as per BMS system along with submission of bank guarantee of 5% in lieu of release of retention amount.

c) Please note that you have to abide by the rules & regulations of PF, ESI, Workmen's Compensation Act, Minimum Wages Act, and Factories Act and follow Safety Rules for workers & will have to pay the necessary premium / installments to the concerned authorities, & keep the client indemnified for any consequences.

d) Please note that the order will to be placed for Part Description: ARC for items mentioned as per the specifications and rates attached in annexure 1.

TOTAL BASIC AMOUNT = RS. 46,06,000.00

NOTE- GST shall be extra at 18%.

e) Actual site measurements to be taken by the party before executing the work.

f) Please note that the basic approval amount is NOT the PO value. PO will be issued on individual approval and case to case basis. This approval amount may vary (i.e. increase or decrease) based on TML business requirement.

g) Material & Labour in party's scope of work.

h) TML reserves the right to reject/stop the material and/or work if found that the quality of work is not as per specifications.

i) Party to ensure that they shall undertake / execute item which is not in attached schedule / scope of work only after written approval by TML.

j) M/s Nihva to ensure that the billed amount for work shall not exceed the Total Order Value of P.O.

k) The party should necessarily submit job card / testing & commissioning/ quality reports along with bills / invoice.

l) Please note that material loading, unloading, scaffolding erection and dismantling, transport of material etc at site is in your scope of works.

m) Once SAP PO is issued based on site specific requirement; party has to measure the actual sizes at site location before ordering the material in consultation with TML engineer.

n) Adequate resources (Manpower- technical, safety, supervisor and workers, Material, safe to operate Machinery-Tools and tackles) shall be deployed at site.

o) TML may divert the business to other vendor if found necessary based on the parameters of quality, safety and timeline adherence.

p) The documents sent along with enquiry RFQ are integral part of this contract document and shall be referred to for specifications, quality and safety compliance.

q) During this contract period you shall ensure your company abides by the Environmental Policy of Tata Motors Ltd., and follow the Code of Conduct for Suppliers/ Contractors.

r) Safety: Your staff at work shall ensure that they follow all the safety rules & regulations at the work place. The machinery / equipment's / tools & tackles shall be certified for use by competent authority. You will arrange for Safety helmets, safety belts & safety shoes, for your workers and ensure its use during work. Any safety offence or deviation from safety rules, regulations & practices shall call for penalty as below:

   First offence: Rs. 10,000/-
   Second offence: Rs. 25, 000/-
   Third offence: Rs. 50,000/-
   Fourth offence: Cancellation of Contract.

Yours Faithfully,
For TATA MOTORS LTD.

S.D. Kale
Head Construction
Encl: Annexure-01A,1B & 1C Technical details.
Annexure-02 Pricing details.

Annexure-II.	
Enclosed to CD\127\21-22\NI-2109\048	

Annual rate contract (ARC) for Supply, Installation,Testing & Commissioning of Double skinned Galvanised shutters with PUF insulation for temperature controll(23 degree +/- 3 degree) having Motorisation system and Automated Rapid roll up shutters, automated fully glazed sliding doors of various sizes and Automatic Sliding Doors (partly glazed and partly panelled) biparting and telescopic and G. I. Rolling shutters at TATA Motors Ltd. Pune for a period from 01-Jan-2022 to 31-Dec-2023.

	Name of Party ---------->			M/s.NIHVA Technologies	
				Supply Rate in Rs.	Installation Rate in Rs. *
Sr. No.	Description of Item	Nomenclature/Description	Unit	Approved Rate	Approved Rate
1	Supply, Installation,Testing & Commissioning of Double skinned Galvanised shutters with PUF insulation for temperature controll(23 degree +/- 3 degree) of various sizes having Motorisation system.	Puf Insulated double skin G.I.shutters.	Sq.m	18000	0
2	Supply, Installation,Testing & Commissioning of Automated Rapid roll up shutter of various sizes.	Rapid roll up PVC shutters	Sq.m	32500	0
3	Supply, Installation,Testing & Commissioning of Automatic Sliding Doors (Fully Glazed toughned)of various sizes having BIPARTING OPENING.	Fully Glazed toughned shutter	Sq.m	46000	0

Annexure-II.					
Enclosed to CD\127\21-22\NI-2109\048					
Annual rate contract (ARC) for Supply, Installation,Testing & Commissioning of Double skinned Galvanised shutters with PUF insulation for temperature controll(23 degree +/- 3 degree) having Motorisation system and Automated Rapid roll up shutters, automated fully glazed sliding doors of various sizes and Automatic Sliding Doors (partly glazed and partly panelled) biparting and telescopic and G. I. Rolling shutters at TATA Motors Ltd. Pune for a period from 01-Jan-2022 to 31-Dec-2023.					
	Name of Party ---------->			M/s.NIHVA Technologies	
				Supply Rate in Rs.	Installation Rate in Rs.
Sr. No.	Description of Item	Nomenclature/Description	Unit	Approved Rate	Approved Rate
4	Design, Supply, Installation & Commissioning of Automatic Sliding Doors (partly glazed and partly panelled -BIPARTING OPENING with TATA BLUE Colour/Equivalent door frame	Biparting Opening door	Sq.m	46000	0
5	Design, Supply, Installation & Commissioning of Automatic Sliding Doors (partly glazed and partly panelled -SLIDING SINGLE SHUTTER DOOR OPENING (TELESCOPIC) with TATA BLUE Colour/Equivalent door frame.	Sliding door	Sq.m	58000	0
6	Design, Supply, Installation & Commissioning of duel operational Motorised G.I.Rolling Shutter with Jielong/ Equivalent make 1 HP motor etc.complete.	Motorised G.I.rolling shutter with Jielong make motor.	Sq.m	17500	0
	*No separate payment for Installation. It is included in supply. GST 18% extra.				

Enclosed to CD/127/21-22/NI2109/048			
Technical Annexure for Sr.no.1.			
Supply, Installation,Testing & Commissioning of Double skinned Galvanised shutters with PUF insulation for temperature controll(23 degree +/- 3 degree) of various sizes having Motorisation system and Magnetic Loop Detector.			
	Name of Vendor		
		TML Requirement	NIHVA
	Double skinned Puf Insulated Motorised G.I.Rolling shutters		OK
Sr. No	Item	Specification / Minimum Requirement size in meters(LengthXHeight)-Quantity	Ok
1	Double skinned Galvanised Puf Insulated Motorised Rolling shutter of sizes as mentioned below.	size as per site requirements. having ONLY Motorisation system and NO AUTOMATION	OK
	Detailed Location/ size: ------>	As per site requirements./General size 3000 mm X 3000 mm or 3000 mm W x 4000 mm H (but may vary based on site conditions)	OK
I	Type of Door-Purpose	Double skinned Galvanised shutters with PUF insulation for better thermal insulation with energy efficiency and durability.	Puff Infill Double Wall Rolling shutter.
	MODEL:	As Suggested by Vendor	NIHVA Techonology
	MAKE:	As Suggested by Vendor	NIHVA DWRS-
1	Clear Opening (Length x height)	As per site requirements.	3 x 3 mtr or 3 x 4 mtr.
2	Interlocking	As per site requirements.	We can proivde at extra cost.
3	Magnetic Loop Detector	Required.	OK
4	Magnetic Radar	Not required.	OK
5	Motorisation	Required.	Yes.
6	Frame material	Pre coated Galvanized steel profile	slats are with Pri-Coated Puff infill Shutters.

Technical Annexure for Sr.no.1.			
Supply, Installation,Testing & Commissioning of Double skinned Galvanised shutters with PUF insulation for temperature controll(23 degree +/- 3 degree) of various sizes having Motorisation system and Magnetic Loop Detector.			
	Name of Vendor		
		TML Requirement	NIHVA
	Double skinned Puf Insulated Motorised G.I.Rolling shutters		OK
Sr. No	Item	Specification / Minimum Requirement size in meters(LengthXHeight)-Quantity	Ok
7	Fabric/Metal sheet colour	Metal Sheet Colour: Tata Blue (RAL 5015) or as directed by TML Engg./Shop Incharge.It shall be certified by TML user/site incharge after ordering.	OK
8	Aesthetics	The shutters shall be aesthetically appealing in colour/shed and parts finish quality shall be excellent.	It is, we shall proivde the drawing / samples for approval.
9	Visual Panels/windows -	Double glasss glazing vision panel for visibility.(Two rows at appropriate level).	ok
10	Bottom rail	To be provided with extruded rubber bottom seal that will seal against the door when the door is fully closed avoiding cooling loss and maintaining inner temperature.	it Comes with EPDM Heavy duty gasket.
11	Operating Mechanism For opening & closing	Required from both sides	Ok Both side push button will be proivded.
12	Push buttons	Required from both sides	Ok Both side push button will be proivded.
13	In case of power failure	Manual operation required Door should operate Manually through hand crank.	Hand Chain / Crank will be proivided from Inside only. Where the motor is installed
14	Yellow Flashing light	Required from both sides	Ok We can proivde both side.
15	Opening and closing Speed of door	Opening speed shall not be more than-1.0 m/s. Closing speed shall not be more than-0.8 m/s.	It will be max 75-200 mm per sec.
16	Motor Details-Necessory warranty on parts shall be submitted whille handing over.	Supplier Should give make & details.	Yes.
17	G.I.sheet Specification (Make, thickness, density,temp. resistant, breaking strength)	Minimum 0.5 mm thick G.I.sheet thickness.Double skinned with PUF insulation.The type of PUF insulation shall comply with safety and environment standards.Thickness of insulation shall be 20-25 mm thick.Density of puf insulation shall be minimum 40Kg/M3.Make of insulation Rockwool/Kimmco/Twiga.Vendor to choose the right thickness of insulation as per design requirements.	18-19mm Puff Infill Slats rest is ok

Technical Annexure for Sr.no.1.			
Supply, Installation,Testing & Commissioning of Double skinned Galvanised shutters with PUF insulation for temperature controll(23 degree +/- 3 degree) of various sizes having Motorisation system and Magnetic Loop Detector.			
	Name of Vendor		
		TML Requirement	NIHVA
	Double skinned Puf Insulated Motorised G.I.Rolling shutters		OK
Sr. No	Item	Specification / Minimum Requirement size in meters(LengthXHeight)-Quantity	Ok
18	Shutter locking arrangement	Required from outside.	Ok.
19	Air pressure that door can withstand	Please mention	50 Pas.
20	Wind pressure that door can withstand	Min 200 km/Hr.	120 kmpl
21	Temperature to be maintained inside the area	23 degree centigrade +/- 3 degree is the requirement. This Temperature requirement criteria is Criticle.	Ok
22	Test certificate	After installation and commissioning a test report and work completion certificate along with warranties shall be issued and handed over to user.	Yes.
23	Shutter usage in no. of times in a day.	Regular usage for everyday operations.	Ok
24	Hood cover & Motor cover	Required.	Ok
25	Edge safety protector	Required.	We can proivde at extra cost.
26	RCC frame/Support structure	If required TML Shall provide	It will be TML scope

Technical Annexure for Sr.no.1.			
Supply, Installation,Testing & Commissioning of Double skinned Galvanised shutters with PUF insulation for temperature controll(23 degree +/- 3 degree) of various sizes having Motorisation system and Magnetic Loop Detector.			
	Name of Vendor		
		TML Requirement	NIHVA
	Double skinned Puf Insulated Motorised G.I.Rolling shutters		OK
Sr. No	Item	Specification / Minimum Requirement size in meters(LengthXHeight)-Quantity	Ok
27	Warranty	Minimum 18 months from date of commissioning/compliance of snag points and handing over.	OK
28	Delivery Period	two weeks after order issuance/LOI.	3-4 Weeks from Drawing Approval.
29	Installation and commissioning	Within 10 days after material delivery at site.	Ok

Enclosed to CD/127/21-22/NI2109/048			
Technical Annexure for Sr.no.2.			
Supply, Installation,Testing & Commissioning of Automated Rapid roll up shutters of various sizes			
	Name of Vendor		
		TML Requirement	NIHVA
	Automated Rapid Roll up shutter	Automated Rapid Roll up shutter	
Sr. No	Item	Specification / Minimum Requirement	
	Detailed Location/ Size : --------->	As per site requirements./General size 3000 mm X 3000 mm or 3000 mm W x 4000 mm H (but may vary based on site conditions)	Ok
I	Type of Door	Automated Rapid Roll up shutter	NIHVA-HSD
	MODEL:	Please mention details	NIHVA HSD
	MAKE:	Please mention details	NIHVA Make
1	Clear Opening (width x height) in mm.	As per site requirements.	As per the Quotation (3000 x 3000 mm or 3000 x 4000 mm) only
2	Frame material	Pre coated Galvanized steel profile	Ok
3	Fabric	PVC Sheet Colour: Tata Blue (RAL 5015) or as directed by TML Engg./Shop Incharge	Ok
4	Visual Panels -	PVC see through panels at Intermediate levels.	It will be at 1.3 mtr form FFL. 1 Row
5	Aesthetics	The shutters shall be aesthetically appealing in colour/shed and parts finish	Yes It will be as per drawing submission
6	Operating Mechanism For opening & closing	Required from both sides	Push Button from Both side
7	Bottom rail	To be provided with extruded rubber bottom seal that will seal against the door when the door is fully closed avoiding cooling loss and maintaining inner temperature.	It will be with heavy duty EPDM Gasket
8	Push buttons	Required from both sides(in case of manual operations.)	Push Button from Both side
9	Sensors : Microwave Radar with function discrimination	Microwave Radar Required from both sides: Supplier to prove safe working of doors for forklift /manual movement with active Microwave Radar	Yes.
10	Magnetic Loop detector	Required from both sides	ok

Enclosed to CD/127/21-22/NI2109/048			
Technical Annexure for Sr.no.2.			
Supply, Installation,Testing & Commissioning of Automated Rapid roll up shutters of various sizes			
	Name of Vendor		
		TML Requirement	NIHVA
	Automated Rapid Roll up shutter	Automated Rapid Roll up shutter	
Sr. No	Item	Specification / Minimum Requirement	
11	emergency condition	push to open and auto retracting system required(safety edge)	Safety Edge will be provided.
12	Photo sensor/Photocells for safety purpose	Active photo sensor required from both sides - 2 Pair for each door.	Ok
13	Impact Sensor , Safety edge protector , anti collision	Required from both sides & should be active	Hand Chain / Crank will be proivided from Inside only. Where the motor is installed
14	Anti - crash mechanism	Required	Ok
15	In case of power failure	Manual operation required Door should operate Manually through hand crank.	Hand crank will be from inside where motor is inatalled.
16	Yellow Flashing light	Required from both the sides.	Yes
17	Remote control / Receiver	Not required	Ok
18	Key Switch (Not Required)	Not required	Ok
19	UPS + Battery	Not required	Ok
20	Shutter locking arrangement	Required from outside.	Key switch needs to be added with extra cost.
21	Opening and closing Speed of door	Opening-1 m/s Closing-0.8 m/s	Ok
22	Suitable for UV exposure and heat resistant)	PVC fabric should resist Ultra Violet rays	Ok, but UV can damage the Fabric Color shade
23	Motor Details-Necessory warranty on parts shall be submitted whille handing over.	Supplier Should give make & details.	Ok
24	PVC Fabric Specification (Make, thickness, density, weight per Sq.m; temp. resistant, breaking strength)	Thickness:1mm, PVC weight: 900 gram per Sqm Temp. Resistance: -0 to 70 degree Centigrade	Ok, -22 to + 70 Dig
25	Air pressure that door can withstand	Please mention	25 pas.
26	Wind pressure that door can withstand	Please mention(Min 100 km/Hr	100 kmpl (Higher will be on request with extra cost)
27	Temperature to be maintained inside the	23 degree centigrade +/- 3 degree is the requirement.	Ok

Enclosed to CD/127/21-22/NI2109/048			
Technical Annexure for Sr.no.2.			
Supply, Installation,Testing & Commissioning of Automated Rapid roll up shutters of various sizes			
	Name of Vendor		
		TML Requirement	NIHVA
	Automated Rapid Roll up shutter	Automated Rapid Roll up shutter	
Sr. No	Item	Specification / Minimum Requirement	
28	Test certificate	After installation and commissioning a test report and work completion certificate along with warranties shall be issued and handed over to user.	Ok
29	Shutter usage in no. of times in a day.	Regular usage in day to day operations.	Ok
30	Hood cover & Motor cover	Required.	Ok
31	RCC frame/Support structure	If required TML Shall provide	TML Scope only
32	Warranty	Minimum 18 months from date of commissioning/compliance of snag points and handing over	Ok
33	Delivery Period	**two weeks after order issuance/LOI.**	8-9 Week from Drawing approval
34	Installation and commissioning	**Within 10 days after material delivery at site.**	Ok

Enclosed to CD/127/21-22/NI2109/048			
Technical Annexure for Sr.no.3.			
Supply, Installation,Testing & Commissioning of Automatic Sliding Doors (Fully Glazed toughned) of various sizes.			
1	Name of Party:-		
Sr. No.	Description	Specification / Minimum Requirement by TMI	NIHVA Technology
A.	Type	BIPARTING OPENING	
	MODEL:		NIHVA-Sliding Glass Door
	MAKE:		NIHVA
	Features / Technical Specs		
1	Clear Opening (width	As per site requirements.	Ok
2	Overall Dimensions of Door Size (width x height)	General size 2000 mm W x 2500 mm H (May vary based on site conditions)	Ok (Should not vary more than 200mm)
3	Type	Sliding double shutter doo	Ok
4	Door type	Fully glazed toughned glas	Ok
5	Details of glass	Saint Gobain make toughned glass.Glass thickness 12 mm	ok
6	Patch Fittings	All S.S.patch fittings/accessories shall be Hetit/Dorma fittings.	Ok
7	Opening speed	100-300 mm/second. Speed shall be adjustable.	Ok
8	Closing speed	100-200 mm/second. Speed shall be	Ok
9	Operating Temperatu	Range -20 to +55 degree Centigrade.	Range -20 to 60 Dig
10	Emergency push button	Required	OK.
11	Built in photo cell for safety	Required	Ok
12	Controll Unit	Microprocessor radar based control unit is required.	Yes

1	Name of Party:-		
Sr. No.	Description	Specification / Minimum Requirement by TMI	NIHVA Technology
13	Door locking/Deactivitatio n facillity	Door deactivation facillity(either in Open or closed position) shall be made available. Also a door locking	Yes
B	Installation	In vendor scope	Ok
C	Basic Cost		
D	Freight / Transport	Should be included in vendor cost FOR at site.	Hand Chain / Crank will be proivided from Inside only. Where the motor is installed
E	Packing & Forwarding at ____	Should be included in vendor cost.	Ok
F	Transit Insurance	Should be included in vendor cost .	Ok
G	warranty after installation	18 months	Ok
1	Delivery	two weeks after PO/LOI.	3-4 Weeks
2	Installation	within 7 days of delivery.	Ok
3	Guarantee	12 months	Ok

*GST extra.



Enclosed to CD/127/21-22/NI2109/048				
Technical Annexure for Sr.no.4 & 5.				
Design, Supply, Installation & Commissioning of Automatic Sliding Doors (partly glazed and partly panelled with Tata Blue colour/Equivalent frame) BIPARTING OPENING and TELESCOPIC OPENING at at various locations at Tata Motors Pimpri pune.				
Sr. No.	Description	Specification / Minimum Requirement by TML.	NIHVA	NIHVA
A.	Type		Biparting Opening	Telescopi c Opening
I]	MODEL:	NIHVA Glass Door BiParting		Teliscopic
II]	MAKE:			
III]	Features / Technical Specs			
1	Clear Opening (width x height)	General size 2000 mm W x 2500 mm H (May vary based on site conditions)	Ok But should not be more than 200mm	ok
2	Overall Dimensions of Door Size (width x height)	2000 mm x 2500 mm (May vary as per site conditions)	Ok But should not be more than 200mm	ok
3a	Type	Sliding double shutter door	Ok	NA
3b	Type	Telescopic single shutter door(2000 mm X 3000 mm)	NA	Ok
4	Door type	Party glazed and partly panelled.(Refer image below)	Ok	Ok
5	Details of glass & Prelaminated particle board.	Glass panel height-2.0 m Panel board panel -1.0 m.	Ok	Ok
6	Frames	Heavy Aluminium sections as per design	Ok	Ok
7	Finish Type of door frame	Powder coated frame Tata Blue/Equivalent shed as	Ok	Ok
8	Glass Thickness and Type	8 mm thick toughend glass.Saint Gobain make	Ok	Ok
9	Prelaminated Particle board /Bakelite board	8 mm thick	Ok	Ok
10	Opening speed	100-300 mm/second. Speed shall be adjustable.	Ok	Ok
11	Closing speed	100-200 mm/second. Speed shall be adjustable.	100-300MM	100-300MM
12	Release of Manual Opening	A handle is to be provided	OK	OK
13	Operating Temperature	As per standard.(Please confirm)	Tem -22 to 60 Dig Cell	Tem -22 to 60 Dig Cell
14	Emergency push button	Required	OK	ok
15	Provision to keep the door in closed or Open position.	Required	Hand Chain / Crank will be proivided from Inside only. Where the	ok
16	Built in photo cell for safety	Required	ok	ok

Sr. No.	Description	Specification / Minimum Requirement by TML.	NIHVA	NIHVA
A.	Type		Biparting Opening	Telescopic Opening
17	Controll Unit	Microprocessor radar based control unit	Ok	Ok
18	Installation	In vendor scope	Ok	Ok
19	Freight / Transport	Should be included in vendor cost FOR at site	Ok	Ok
20	Packing & Forwarding at __	Should be included in vendor cost	Ok	Ok
21	Transit Insurance	Should be included in vendor cost	Ok	Ok
22	warranty after installation	18 months	Ok	Ok



SAMPLE PHOTO-
TELESCOPIC OPENING



SAMPLE PHOTO-BIPARTING OPENING

Enclosed to CD/127/21-22/NI2109/048			
Technical Annexure for Sr.no.6.			
Design, Supply, Installation & Commissioning of Dual operational (Manually & motorised) G.I.Rolling shutters at various locations at Tata Motors Pimpri pune.			
1			
Sr. No.	Description	Specification / Minimum Requirement by TML.	NIHVA Technology
A.	Type		
I]	MODEL:		NIHVA - SWRS
II]	MAKE:		NIHVA Make
III]	Features / Technical Specs		
1	Clear Opening (width x h	As per site requirements./General size 3000 mm X 3000 mm or 3000 mm W x 4000 mm H (but may vary based on site conditions).	ok
2	Overall Dimensions of Door Size (width x height)	As per site requirements./General size 3000 mm X 3000 mm or 3000 mm W x 4000 mm H (but may vary based on site conditions).	ok
3	Type	G.I.rolling shutter motorised and also by manual operation.	Ok
4	G.I. SLATS:	Thickness 20 Gauge (minimum thickness1.006 mm) Width 75 mm. Length Clear Opening + 200 mm	Ok
5	G.I.Top COVER:	Thickness 18 Gauge (Minimum 1.31 mm). Length Clear Opening + 600 mm	0.9mm. With length of +600mm
6	G.I. GUIDES:	Made out of G.I. sheet 10 gauge (Minimum 3.51 mm).Size 125 X 125 mm.	GI 3.5 mm with 75 - 100 mm x 30mm.
7	BOTTOM RAIL	Thickness 14 G (1.994 mm) Angle (25 x 25 x 5) welded at bottom. SPRING: As required. RED OXIDE PAINT: One coat red oxide paint of approved company to M.S. parts.	ok
8	M.S. Handles	02 Nos.	ok
9	Locking arrangements.	Required.	Yes.

Sr. No.	Description	Specification / Minimum Requirement by TML.	NIHVA Technology
A.	Type		
10	MOTORIZING SYSTEM:	3 Phase JIELONG make/Equivalent , 1 hp geared motor, control panel board, forward reverse starter, limit switches, electric fitting and fixtures, connecting shaft with gear box, and dual system so that the shutter can be operated by handle in case of motor or electric failure, etc. complete.	Ok
11	Installation	In vendor scope	Yes
12	Freight / Transport	Should be included in vendor cost FOR at site	Ok
13	Packing & Forwarding at ——	Should be included in vendor cost	Ok
14	Transit Insurance	Should be included in vendor cost	Ok
15	warranty after installation	18 months	Ok



SAMPLE PHOTO