AMIT ENGINEERING

MATERIAL HANDLING BUSINESS

1378, Pawar Vasti, Opp. Saraswati school, Chikhali, Pune - 412114 (India).

Tel - +91-20-27491070.Fax - +91-20-27492002,

E-mail - amitengineering@gmail.com.Website:-www.amitlifttrucks.com

(A D&B Registered Company)

QUOTATION

AE/MG/911-1
Date: 9/11/2017

To,
NIHVA technologies Pvt. Ltd.
187, G-Block, Thermax chowk, MIDC
Chinchwad, Pune – 411019

Kind Attn- Mr Ameet Kurhade Purchase Manager

Subject:-Quotation for Hydraulic Type Goods Lift.

Dear Sir,
We are very much thankful to you for your enquiry for Goods Lift.
We are pleased to quote for the same as under

Technical Specifications	**Qty.**	**Rate in Rs /each**
1) **Hydraulic Goods Type -1** Capacity :- 2000 kg Cage platform:- 2000 X 2000 mm Lift height:- 5000mm(5m) Cage collapsible door:- Tube structure with on side hinged	1 no	**5,15,000/-**
2) Safety railing L 2500 X H 2000 mm	4 set	**16,000/-**

Scope of supply: - Design, manufacturing, supply & installation at your location. Any civil work would in your scope. crane for installation would be in client scope.
3 phase /2 phase supply required at the time of installation.
Hydraulic Power pack – Hydraulic power pack will be operated by 3 phase Motor, all controls will be 24V DC ,Control panel would be on power pack, separate operating pendent (station) would be given along with equipment.

Electric Controls - Siemens, electric motor- Siemens/ Bharat Bijlee , Suction line oil filter –Hydroline, hydraulic gear pump – Bosch Rexroth / Dowty , Pressure Relief Valve-

Polyhydron, High pressure hoses – Parker, Load hold valve – Tucson/ Hydex,

Hydraulic oil- Servo / HPCL, limit switch etc.

Raw Material for Structure – MS Structure would be as per IS Standard.

Safety Features of Goods Lift Table

- Overload hydraulic valve will be provided in hydraulic to ensure the equipment will not lift if loaded beyond its rated load capacity.
- Maximum height limit switch along with mechanical stoppers are provided to ensure lift is not raised beyond its maximum height.
- Manual lowering valve to lower the scissor lift platform to its minimum down position in case of power failure.

Terms & Conditions

1) Delivery :-6-7 weeks on receipt on receipt of order & advance
2) Validity :- 30 days
3) Taxes :- GST 28 % extra.
4) Transport :- to your account
5) Payment :- 60 % advance along with purchase order,40% after completion of manufacturing and trials in our works against proforma invoice before dispatch,
6) Installation and Training: - Rs 60,000/- Extra with in Pune.Any civil work will be in your scope. Crane for unloading and installation of Goods Lift parts will be provided by you**.**
7) Warranty : - 12 months from date of supply against any manufacturing defect.
8) Trials :- At our works before dispatch by your officials.

We hope that you will find the above quotation is in order and competitive. We request to release the order at the earliest**.**

Thanking you,
Yours Faithfully
For Amit Engineering

Ajit Patil (Cell-09422306343)