NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Conglomerate
off no 13,bldg. no A,Zambharae Heritage ,
Chavhan Nagar,Dhankawadi Pune 411043

Date : 11.11.2020
Quote NO : SQT.20.21.2774R
Kind Attn : Harish Pitambar Chahan
Email Id : conglomerate.punegmail.com
Contact No: 9881032643

Subject : Quotation for High Speed Door, Boom Barrier and Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	NIHVA Make High Speed Door	3650	4419	1	3,50,000	3,50,000	20,000	20,000
~~2~~	~~Boom Barrier~~	~~6000~~		~~1~~	-	-	-	-
~~3~~	~~Motorized Sliding Gate~~	~~8230~~	~~1830~~	~~1~~	-	-	-	-
				Total		**3,50,000**		**20,000**
	P&F Charges			3%		**10,500**		
	Total Without Taxes					**3,60,500**		**20,000**
	GST Extra @ 18%			18%		64,890		3,600
	Total With Taxes					**4,25,390**		**23,600**
	Total Supply + Installation with Taxes							**4,48,990**
4	Transportation Charges					**Rs 5,000 Extra**		
5	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

High Speed Doors

- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels

Sr .No.	Specification	High Speed Doors
1	**Use**	Internal Door
2	**Speed**	Inverter Motion system to adjust different speeds, with progressive control of acceleration
3	**Opening speed**	upto 3 m/s
4	**Closing speed**	0.8 m/s
5	**Control Panel**	4 Push Button operated
6	**Security Features**	EN 13241-1 Standard
7	**Resistance to wind load**	EN12424 upto class 1
8	**Curtain**	Fabric Transparent PVC section
9	**Vision Panel**	as per enclosed picture
10	**Guide Material**	Aluminum
11	**Hood Cover**	GI
12	**Motor Cover**	GI
13	**Operator & Control**	German Make Motor
14	**Connecting Voltage**	220V , 1Ph , N
15	**Open-Stop-Close Button**	Standarad
16	**Protection Category**	IP 54 / IP 65
17	**Power Consumption**	0.75 kw Motor
18	**Emergency Off Button**	Standard
19	**Closing Zone Monitoring**	Optical Safety edge
20	**External Route Monitoring**	Photocell
21	**Emergency Opening**	Crank Handle

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7-8 weeks for High Speed Doors from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Sneha Bharane on 8551035333.**

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd