NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chin
Pune – 411019

Date : 22.12.2020
Quote NO : SQT.20.21.
Kind Attn : Mr. Vijay Tarak
Email Id : sales@nihva.com
Contact No: 8551093333

Subject : Quotation for Double Leaf BI PARTING Telescopic Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Double Leaf BI PARTING Telescopic Sliding Gate	17500	1800	1	940,000	940,000	20,000	20,000
				Total		**940,000**		**20,000**
4			P&F Charges	3%		28,200		
			Total Without Taxes			968,200		20,000
			GST Extra @ 18%	18%		174,276.00		3,600
			Total With Taxes			**1,142,476**		**23,600**
5			Transportation Charges			In Client Scope		
6			Unloading Charges @ Site			In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

2 Leaf Bi-Parting Telescopic Sliding Gate

Sr .No.	Specification	2 Leaf Bi-Parting Telescopic Sliding Gate
1	Door type	Motorised Double Leaf Bi-Parting Telescopic Sliding Gate
2	Master Leaf Size	5880 X 1800 mm
3	1 ST Leaf Size	5270 X 1800 mm
4	Opening Direction	Horizontal - from left to right or reverse
5	Mounting Location area	Inside area
6	Design Pattern	Standard Tubular Design Pattern
7	Outer Frame Tube Sizes	72X72X3.2 THK SQ. TUBE
8	Internal Vertical Tube Sizes	25X25X2.6 MM THK SQ. TUBE
9	For Post	72X72X3.2 THK SQ. TUBE
10	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
11	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings
12	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
13	Painting	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
14	Control Panel	2 Nos Operating Station.(Motor Panel and Security Room)
15	Operation	By Telescopic Mechanism
16	Motor Make	BFT - Italian Make
17	Accessories	1. Limit Switch for Cut out when Gate is fully Closed
		2. Flashing Light
		3. Hooter
		4. Photocell

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Front Sale-Contact No** For any further Clarification /Information in this Concern.

With Best Regards
Pradeep Shinde
7219206333
For NIHVA Technologies Pvt Ltd