NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

L&T Hydrocarbon Engineering Ltd
West Block, Ground Floor,
L&T Knowledge City, N.H. No. 8,
Vadodara, Gujarat, India.

Date : 31.01.2020
Quote NO : SQT19-20.2335R3
Kind Attn : Mr. Ankit Garg
Email Id : Ankit.Garg@Larsentoubro.com
Contact No: **8700082601**

Subject : Revised Quotation for Dock Leveller

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size			Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	Clear Depth (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Dock Leveller 6 Ton	2000	5500	800	1	3,42,500	3,42,500	-	-
2	Spare Motor	-	-	-	1	1,00,000	1,00,000	-	-
					Total		**4,42,500**		**-**
					P&F Charges	3%	**13,275**		
					Total Without Taxes		**4,55,775**		**-**
					GST Extra @ 18%	18%	82,040		-
					Total With Taxes		**5,37,815**		**IN LTHE Scope**
					Total Supply + Installation With Taxes				**5,37,815**
3					Transportation Charges		**In Client Scope**		
4					Unloading Charges @ Site		**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Dock Leveler



Sr. No.	Description	Specifications
1	Capacity	6 Ton (Dynamic)
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Standpost Mount
5	Loading platform height from road	1100mm
6	Travel above & below dock level	(+) 600 / (-) 600 mm
7	Platform Size (W x L)	2000 mm x 5500 mm
8	Lip size (W x L)	2000 x 630 mm
9	Shut Height	800mm
10	Overall length	2000mm x 5500mm + Lip Length (630mm)
11	Maximum slope can be achieved	Deg 6
12	Clear Pit dimensions (W x L x D)	(W) 2050mm x (L) 5550 mm x (D)805 mm
13	Hydraulic power pack	Standard
14	Driver type	Direct by electric Motor
15	Motor Ratings	1 H.P
16	Pump design flow	2.5 LPM
17	Pump pressure	120 bar Operating 200 bar Max.
18	Safety valve set pressure	120 Kg/cm²
19	Pump Type	Gear
20	Volume of oil receiver	7 Lit
21	No Of Deck cylinder	2 No
22	Lip Cylinder	1 No
23	Dock Bumper	Pair of Dock Bumper

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Terms Aggred by NIHVA & Discussed on mail

Sr. No.	Terms Aggred By NIHVA & Discussed on Mail (All Included in above Offer)
1	LTHE informed that Dock leveler is installed at approx. 1.1 mtr height from FFL and it should be operate-able in the range of +600 mm to -600 mm under the safe operating conditions. As informed by customer drums will be loaded in the small tempos to ship container. Accordingly M/s Nohva has to design the dock leveler. M/s Nihva will check for the same and revert. If required M/s Nihva will check by increasing the Dock length from 2500 mm (Kindly note that Platform dimension is 7000 X 7000 mm). **(Yes Confirmed)**
2	LTHE informed that Dock leveler shall be designed for safe working conditions. Max angle of safe working conditions to be considered as 7 degree. **(Yes Confirmed)**
3	M/s Nihva confirmed to offer visual, dimension and functional check of dock leveler at their shop before dispatch to LTHE appointed TPIA. **(Yes Confirmed)**
4	LTHE informed to provide the offer for safe area working conditions. **(Yes Confirmed)**
5	LTHE informed that single point 3 phase power supply will be provided. Further distribution from Local control panel to motor or any component of dock leveler will be in M/s Nihvar scope of supply. Also M/s Nihva will provide conduit for the cable for supplier scope of supply. **(Yes Confirmed)**
6	LTHE informed that single point 3 phase power supply will be provided. Further distribution from Local control panel to motor or any component of dock leveler will be in M/s Nihvar scope of supply. Also M/s Nihva will provide conduit for the cable for supplier scope of supply. **(Yes Confirmed)**
7	M/s Nihva informed that first fill hydraulic oil will be supplied by them. **(Yes Confirmed)**
8	M/s Nihva informed that there is no pneumatic air requirement. LTHE noted. **(Yes Confirmed)**
9	LTHE will provide the Civil Pit at site as per dimensions provided by M/s Nihva in their drawings. Installation will be carried out by LTHE in the supervision of supplier. M/s Nihva will submit the drawing for LTHE review. **(Yes Confirmed)**
10	M/s NIHVA to provide sign and stamp copy of no deviation form, Scope table, Proven track record. **(Yes Confirmed)**
11	M/s NIHVA to confirm that offered dock leveler shall be suitable for outdoor installation with direct Exposure to sunlight. **(Yes Confirmed)**
12	All Instruments shall be suitable to Hazardous area Zone 1, Group IIA/IIB, T3, IP66. **(Yes Confirmed)**
13	M/s NIHVA to Consider Safe Area for Electrical Equipment. Motor shall be IP-55 minimum. **(Yes Confirmed)**
14	LTHE informed to include the supply of conduit in scope of supply. M/s Nihva will provide the cut out details in GAD to be kept in Dock leveller foundation. M/s Nihva agreed for the same. **(Yes Confirmed)**
15	LTHE informed to provide the necessary arrangements required for installation of dock leveller like channels etc. in scope of supply. M/s Nihva will indicate the details of grouting or bolting required in foundation at site. M/s Nihva agreed for the same. **(Yes Confirmed)**
16	LTHE asked details for carrying out the Load test at supplier works. M/s Nihva will check with his team about the methodology and will revert. **(Will be carried out at manufacturing unit for +600 & -600)**
17	Power Consumption while Installation **(IN LTHE Scope)**
18	Standpost for Operational control **(IN LTHE Scope)**
19	M/s NIHVA confirmed that there is no recommended spares for 2 year operation. **(Yes Confirmed)**
20	As per clause no. 8.1.1 of doc no.IEGP-6351-8710-PR-000-0017 (Protective painting system) attached with MR, RAL colour shall be Light Grey – RAL 7035. **(Yes Confirmed)**
21	85 dBA Noise Level at 1m distance as per Requisition. **(Yes Confirmed)**
22	LTHE informed to consider Site Temperature of 50 Deg C for Motor Design Purpose for which supplier confirmed that motor is suitable for above site condition. **(Yes Confirmed)**
23	Supply of Anchore mentioned in drawing in **(NIHVA Scope)** Installation of Anchore is in **(LTHE Scope)**
24	Supplier to check and consider standard safety accessories (whichever applicable) in their scope of supply as mentioned below. Kindly mention the safety features (whichever applicable) in the offer which will be provided along with the Dock leveller. Safety stop valve integrated in the lift cylinder: When Dock Loaded and operated the dock will not Operate. MS steel sheet foot side protections. Yellow / black side strips to evidence possible steps when the dock leveler is in use or underneath the dock. Lip support in resting position to prevent any cutting or overwhelm.

Optional Prices (Extra)

Sr. No.	Description	Price
1	Transportation	80,000
2	Extra 2nd Year Warranty Extension	17,500
3	Extra 3rd Year Warranty Extension	27,500

Attachments with respect to mail

Sr. No.	Description	NIHVA Reply
1	PTR (Performance Track Record)	**Attached with mail**
2	GST Registration copy	**Attached with mail**
3	PAN Card copy	**Attached with mail**
4	Manufacturing capacity and facility	**Attached with mail**
5	QA / QC organization chart	**Attached with mail**
6	Financial Standing for last 3 Years	**Attached with mail**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry work required	In Client Scope
5	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment Terms

A) 50% of the basic value of Purchase Order (excluding GST) on fulfilment of below conditions:
• Receipt of an unconditional Purchase Order acceptance copy
• Receipt of Advance Bank Guarantee (ABG) @no cost to LTHE, as per LTHE format (Annexure – V) / approved banks (Annexure – VII) for equivalent amount, valid till 3 months after Purchase Order delivery date goods.
• Receipt of correct Invoice.
• LTHE code – 2 approval on GA drawing from LTHE.

B) Remaining 50% of the basic order value, plus 100% taxes shall be released after dispatch

Note :- All above payments shall be made within 30 days through Wire Transfer from receipt of Original Invoice.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Vivek
8350570333
For NIHVA Technologies Pvt Ltd