NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Amber Enterprises India Limited
Dehradun (Unit 5)

Date : 12.07.2021
Quote NO : **MHE_21.22.0023**
Kind Attn : Mr. Shubham Rajawat
Email Id : shubhamrajawat@ambergroupindia.com
Contact No: 8191010057

Project Name & Location: Amber Enterprises India Limited, Dehradun

Subject : Quotation for Telescopic Belt Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges considering 03 people for 03 days in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Conveyor (Total length 13 mtr)**	**1**	**16,75,000**	**16,75,000**	**70,000**	**70,000**
		Total		**16,75,000**		**70,000**
	P&F Charges	3%		**50,250**		
	Total Without Taxes			**17,25,250**		**70,000**
	GST Extra @ 18%	18%		**3,10,545**		**12,600**
	Total With Taxes			**20,35,795**		**82,600**
2	Transportation Charges					**Extra At Actual**
3	Insurance					**Extra At Actual**
4	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Truck Loader/Unloader Conveyor

Sr. No.	Parameters	Specification
1	Material To Be Handle	Boxes
2	Weight Of Boxes	70 Kg
3	Size of Box/Bags (Max)	830 mm X 755 mm X 575 mm (LxBxH)
4	Capacity	4 boxes per min
5	Type	Fixed
6	Design Capacity	6 boxes per min
7	Belt Width	850 mm
8	Type Of Belt	PVC Belt
9	No. of Extension Stages	3
10	Fixed Length	4000 mm
11	Telescopic Length	8000 mm
12	Total Length	12000 mm
13	Height Of the conveyor	1000 mm
14	Height Adjustment required	Yes
15	Panel make	Local
16	Painting /Powder coating	RAL (Please specify)
17	Max./Min.height of conveyor(Inclination)	Please specify mm
18	Electric component make	Siemens/schnieder
19	MOC of conveyor	MS powder coated/Painted
20	Sensor make(Omron/P&F/Sick/etc)	Omron
21	Belt Motor make	Forbo
22	Belt Gear box make	SEW/Bonfiglioli/PBL
23	Type of Gear Box (Worm/Helical)	Worm
24	Type of Motor(IE2/IE3)	IE2
25	Movement(Forward/Reverse/Both)	Both
26	Mode of lifting(Electric/Hydraulic)	Hydraulic
27	Max Height to lift	Please specify mm

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd