NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ion Exchange (India) Ltd.
ION House, Dr. E. Moses Road, Mahalaxmi, Mumbai-400 011, India.

Date : 11.03.2021
Quote NO : SQT.20.21.2994R2
Kind Attn : Bindiya Chavda
Email Id : bindiya.chavda@ionexchange.co.in
Contact No: 98 9212 2553

Subject : Revised Quotation for Automatic Telescopic Double Leaf Sliding Gate (Laser Cutting on Sheet)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Double Leaf Sliding Gate with Louvers (Laser Cutting on Sheet)**	4500	1800	2	611,000	1,222,000	20,000	40,000
2	**Compound Wall Railing**	4870	850	6	103,000	618,000	20,000	120,000
				Total		**1,840,000**		**160,000**
3	P&F Charges			3%		55,200		
	Total Without Taxes					1,895,200		160,000
	GST Extra @ 18%			18%		341,136.00		28,800
	Total With Taxes					**2,236,336**		**188,800**
4	Transportation Charges					Extra at actual		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Sliding Gate

Sr .No.	Specification	Telescopic Sliding Gate
1	Door type	Motorised Double Leaf Telescopic Sliding Gate
2	Clear Opening gate dimension	(W) 4500 mm X (H) 1800 mm
3	Master Leaf Size	3750 X 1800 mm
4	1 ST Leaf Size	3050 X 1800 mm
5	Opening Direction	Horizontal - from left to right or reverse
6	Mounting Location area	Inside area
7	Design Pattern	Standard Tubular Design Pattern
8	Outer Frame Tube Sizes	100X100X4.5 MM THK SQ. TUBE
9	Internal Vertical Tube Sizes	100X100X4.5 MM THK SQ. TUBE
10	For Post	100X100X4.5 MM THK SQ. TUBE
11	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
12	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings
13	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
14	Painting	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
15	Control Panel	2 Nos Operating Station.(Motor Panel and Security Room)
16	Operation	By Telescopic Mechanism
17	Accessories	1. Limit Switch for Cut out when Gate is fully Closed
		2. Flashing Light
		3. Remote
		4. Hooter
		5. Photocell

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd