NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/18-19/1446 **Date : 09-04-2019**

Deepak Khurana
Delhi

Kind Attention :
Email : deepakkhurana@indecampus.com
Contact No : 9911447800

Project Name And Location : Deharadun

Subject : Quotation for Manual Revolving Door

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer :-

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Manual Operated Revolving Door (100% Imported from Europe)**				
	Manual Revolving Door Silver Anodized Finish - No of Leafs= 3 - Internal Diameter= 2400 mm, - External Diameter = 2496 mm, - Clear Passage Width =1140 mm, - Clear Passage Height = 2400mm, - Canopy height = 100 mm, - Full Door height = 2500 mm, - Door Leaves : Framed 6 mm Tempered Safety Glass - Drum wall : Framed 8.76 mm Laminated Safety Glass Manual Revolving door with 3 leaves, rigid turnstile with Standard frame profile system, drum walls made of glass, ceiling and roof made of Melamine, with Halogen Lamps in ceiling, with Metal Canopy , With Mechanical Locking, Flooring by client Surface Finish: Silver Anodized Finish				
1	Size : (W)2400 x (H)2400 mm	1	No.	15,50,000	15,50,000
	(Supply + Installation)				
	Total Amount				**15,50,000**

GST Pune :	27AAECN0437H1ZM

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the materials to be installed.
2 Be responsible for the safe custody of all materials
3 Provide place to safely store all the tools of installation.
4 Provide change and rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex Pune
2	**P & F Charges**	:	3% Extra
3	**Freight Notes**	:	Extra As applicable
4	**Delivery**	:	14-15 weeks from the date of receipt of confirmed Purchase order, Advance Payment & Drawing Approval
5	**Payment**	:	80% Advance along with Confirmed Purchase Order and balance before delivery
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	GST Extra @18%
8	**Validity**	:	15 days from the date of quotation.
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil o**n **08551096333** For any further Clarification /Information in this Concern.

With Best Regards

Smita Khare
9637991333
For Nihva Technologies Pvt Ltd