NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Rohan Builders (India) Pvt. Ltd.
1 Modibag,Commercial Building,
Ganeshkhind Road, Shivaji Nagar, Pune – 411 016

Project, Location : Dharwad, Karnataka

Date : 29.01.2021
Quote NO : SQT.20.21.2983
Kind Attn : Ajay Mahade
Email Id : inquiry.ho@rohanbuilders.com
Contact No: 9860502997

Subject : Quotation for Motorized Rolling Shutter, Sectional Doors, High Speed Doors, Dock Leveler and Sliding Gates

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorized Single Skin Rolling Shutter**	3000	3500	1	89,000	89,000	15,000	15,000
2	**Motorized Single Skin Rolling Shutter**	4000	4500	1	118,000	118,000	15,000	15,000
3	**Sectional Door**	3000	3500	22	210,000	4,620,000	15,000	330,000
4	**Sectional Door**	4000	4500	12	260,000	3,120,000	15,000	180,000
5	**High Speed Doors**	2700	3500	12	304,000	3,648,000	15,000	180,000
6	**Dock Leveler**	2000	2500	3	200,000	600,000	15,000	45,000
7	**Dock Leveler**	2000	3000	2	220,000	440,000	15,000	30,000
8	**Automatic Single Leaf Sliding Gate**	10000	2000	1	373,000	373,000	20,000	20,000
9	**Automatic Single Leaf Sliding Gate**	12000	2000	1	397,000	397,000	20,000	20,000
10	**Automatic Single Leaf Sliding Gate**	13500	2000	1	413,000	413,000	20,000	20,000
	Total			**56**		**13,818,000**		**855,000**
11	P&F Charges			3%		414,540		
	Total Without Taxes					14,232,540		855,000
	GST Extra @ 18%			18%		2,561,857.20		153,900
	Total With Taxes					**16,794,397**		**1,008,900**
12	Transportation Charges					Extra at atcual		
13	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune - 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Slats with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

NIHVA ASSA ABLOY Sectional Door

Sr. No	Specification	Sectional Door
1	**Vision Windows**	2 Nos at central panel
2	**Opening Direction & Mounting**	Horizontal lift
3	**Opening/Closing Speed**	CDM9 0,28 m/s
4	**Door Material**	GI Steel
5	**Panel Thickness**	42 mm
6	**Filling**	CFC-free polyurethane
7	**Panel colour**	RAL 9002 Grey White Powder coated
8	**Door sealent**	All door sealants made of EPDM rubber, temperature resistant - 30/+70
9	**Panel Flame Retardent standrad**	Flame retardant polyurethane foam according DIN4102-class B2.
10	**Water Penetration**	EN 12425 class 3
11	**Air Permealibity**	EN12426 class 3
12	**Wind Load**	EN21424 class 3
13	**Thermal Transittance**	EN 12428 1.10W /m2K
14	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
15	**Door saftey**	Doors equiped with spring break device
16	**Incase of Power failuer**	Doors to be equiped with quick release fuction
17	**Operator power conumption**	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
18	**Drive Unit & Mounting Type**	Single phase 230V direct drive on shaft
19	**Emergency Operation**	by Disengagement rope manual
20	**Operating Switch**	Up/Down Keypad + stopbutton
21	**Locks : Lock bolt**	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
22	**Environmental Green Product Declaration Certification**	As per ISO 14025 and EN 15804

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune - 411019.

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Dock Leveler

Sr .No.	Specification	Dock Leveller	
1	**Platform Size (W x L)**	**2000 mm x 2500 mm**	**2000 mm x 3000 mm**
2	**Capacity**	**6 Ton**	**6 Ton**
3	**Dock operation mode**	AC power pack hydraulically operated	AC power pack hydraulically operated
4	**Lip operation mode**	Hydraulic	Hydraulic
5	**Operation control**	Through panel	Through panel
6	**Loading platform height from road**	1250mm	1250mm
7	**Travel above & below dock level**	(+) 300 / (-) 250 mm	(+) 300 / (-) 250 mm
8	**Lip size (W x L)**	2000 x 400 mm	2000 x 400 mm
9	**Shut Height**	480 mm	480 mm
10	**Overall length**	2000mm x 2500mm + Lip Length (400mm)	2000mm x 3000mm + Lip Length (400mm)
11	**Maximum slope can be achieved**	0.1	10%
12	**Clear Pit dimensions (W x L x D)**	(W) 2050mm x (L) 2550 mm x (D)485 mm	(W) 2050mm x (L)3000 mm x (D)485 mm
13	**Hydraulic power pack**	Standard	Standard
14	**Driver type**	Direct by electric Motor	Direct by electric Motor
15	**Motor Ratings**	1 H.P	1 H.P
16	**Pump design flow**	2.5 LPM	2.5 LPM
17	**Pump pressure**	120 bar Operating 200 bar Max.	120 bar Operating 200 bar Max.
18	**Safety valve set pressure**	120 Kg/cm²	120 Kg/cm²
19	**Pump Type**	Gear	Gear
20	**Volume of oil receiver**	7 Lit	7 Lit
21	**No Of Deck cylinder**	2 No	2 No
22	**Lip Cylinder**	1 No	1 No
23	**Yellow and Black Strips for Side Guide**	Included	Included

HSD - NIHVA MAKE

- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels

Sr. No	Description	Specifications
1	Use	Internal Door
2	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	Opening speed	upto 3 m/s
4	Closing speed	0.8 m/s
5	Control Panel	4 Push Button operated
6	Security Features	EN 13241-1 Standard
7	Resistance to wind load	EN12424 upto class 1
8	Curtain	Fabric Transparent PVC section
9	Guide Material	Aluminum
10	Hood Cover	GI
11	Motor Cover	GI
12	Operator & Control	German Make Motor
13	Connecting Voltage	220V , 1Ph , N
14	Open-Stop-Close Button	Standarad
15	Protection Category	IP 54
16	Power Consumption	0.75 kw Motor
17	Emergency Off Button	Standard
18	Closing Zone Monitoring	Optical Safety edge
19	External Route Monitoring	Photocell
20	Emergency Opening	Crank Handle

Motorized Single Leaf Sliding Gate

Sr .No.	Specification	Motorized Single Leaf Sliding Gate
1	Door type	Motorized Sliding Gate
2	Opening Direction	Horizontal - from left to right or reverse
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Tube	72 x 72 x 3.2mm MS SQ. TUBE
6	For Post	72 x 72 x 3.2mm MS SQ. TUBE
7	Innear Tube	38x38x3.20mm/40x40x3.2 MS SQ. TUBE
8	Gap Between Tubes	125mm
9	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	El motor make	BFT – Italy (100% imported)
14	Emergency Operation	Manual after turn the switch
15	Operating Switch	Push Button from inside
16	Safety	Photocells, Flashing Light

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune - 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd