NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

PROJECT PROPOSAL

NIHVA TECHNOLOGIES PVT. LTD.

187, G-Block, Thermax chowk, Above Renault Showroom, MIDC
Chinchwad, Pune – 411019.

Customer Name	**PURUSHOTTAM COMPANY PVT LTD**
Project Name	**MANIPULATOR**
Project Location	BHOSARI
Contact Person Name	Mr. NITIN PATIL.
Email Id	design@purushotam.com
Contact Number	+91-9168438686

Contact Person: Mr. Arjun Patil
Mob No.: 8551096333
Email id: arjun.patil@nihva.com
Web: http://www.nihva.com

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Dear Sir,

Thank you for the opportunity and trust shown on “NIHVA” your preferred partner for innovative solutions. This has reference to your above-mentioned requirements as well as our subsequent communication, please find below our best offer.

A. Requirement:
Manipulator of 80kg load capacity.

Technical Specifications: - (For 80 kg Manipulator)

System Drawing: As per attachment

Sr No.	System Description	QTY	
1	**Mechanical Structure**		**1**
	• Base Beam	800 mm	
	• vertical beam	1900 mm	
	• Thrust Bearing	387-1-A-490	
	• horizontal beam	1850 mm	
	• small Arm	1000mm	
	• horizontal arm	1300 mm	
	• **Handle**		
2	**Pneumatic System**		
	• Cylinder 1	500 mm stroke	**2**
	• Cylinder 2	50 mm stroke	**4**
	• Solenoid valves	Festo make	**2**
	• Non-return valves	Festo make	**4**
	• Pneumatic connectors	Festo make	**20**
	• Pneumatic pipe	Dia 12 mm, 10 mm, 8 mm	
3	**Mechanical parts**		**1**
	• LM Rail	750 mm (PMI Make)	**1**
	• LM Shoe		**1**
	• Thrust Bearing	100-1-A-160	**2**

Sr no	Description	Qty	Unit	Rate in INR	Net Amount INR
1	Design, Mfg, Supply and Installation of Manipulator – 80 kg capacity inclusive of Mechanical Structure, Pneumatic system and painting	1	No	398,000	3,98,000
2	Air compressor Capacity: 100PSI, 10cfm	1	No	45000	45,000
Total					**4,43,000**

GST Pune:	**27AAECN0437H1ZM**	**Total Amount**	**4,43,000**

Note: Packing charges will be extra at actual dispatch

E. Drawings Training and warranty

- **Drawing:**

  We will issue a full set of drawings for approval within 2 weeks of receiving the confirmed order and finalized design details.

- **Training:**

  After installation of the Conveyor system, we will train the Clients personnel in the operation and basic maintenance, including the understanding of the error codes on the control system (if applicable).

Warranty:

I. The warranty period is twelve months from the date of installation and commissioning.
II. If a defect arises within the warranty period stated, which is attributable to faulty design,
III. materials or installation workmanship the product will be repaired at our discretion without charge.

IV. This guarantee is subject to proper use of the product and assumes that the product is regularly serviced and maintained by skilled personnel in accordance with the operation and maintenance instructions supplied.

- **Maintenance & Service Agreement:**

  We would suggest that you take advantage of a maintenance and service agreement on the NIHVA products, which will guarantee trouble free operation and speed of response in an emergency. Customized proposals are available on request.

- **Client Scope:**

  1. Transportation
  2. Unloading from truck placement on site.
  3. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

G. Terms and Conditions: -

1. Price	: Ex. Works Pune
2. P & F	: 3 % Extra at the time of delivery.
3. Freight Notes	: Extra as applicable.
4. Delivery	: Within 08 - 10 weeks from date of receipt of confirmed purchase order, advance payment, drawing approval.
5. Payment Terms	: 60% Advance along with confirmed purchase order balance before dispatch.
6. Insurance	: Extra as applicable.
7. GST	: As Applicable on total supply value.
8. Validity	: 15 days from date of quotation.
9. Warranty	: 12 months from date of supply.

Please feel free to contact **Mr. Shailendra Kumar on 9168423687** for any further clarification in this concern.

With Best Regards,

Arjun Patil
8551096333

For NIHVA Technologies Pvt Ltd