NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Mastpro Consulting Engineers Pvt.Ltd
Pune

Date : 13.03.2020
Quote NO : SQT.19.20.2421R2
Kind Attn : Mr. Manesh Dhamale
Email Id : business@mastpro.in
Contact No: 8999667361

Project Name & Location:

Subject : Quotation for Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Single Skin Motorised Rolling Shutter**	2500	2500	1	87,000	87,000	10,000	10,000
2	**Structure + Scaffolding for above Shutter**			1	30,000	30,000	5,000	5,000
				Total		**117,000**		**15,000**
3	P&F Charges on Total Supply Value			3%		**3,510**		
	GST Extra @ 18%			18%		21060		
4	Transportation Charges					**In client scope**		
5	Unloading Charges @ Site					**In client scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Make Single Skin Motorised Rolling Shutter

Sr. No	Description	Specifications
1	Rolling Shutter	Motorised Rolling Shutter with GI steel of thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Curtain Panel	The panel made of 1.0mm thick GI steel
4	Curtain panel size	75mm wide
5	Curtain Profile	Curved
6	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
7	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
8	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
9	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension
10	Hood Cover	Made of GI Sheet Thickness 0.9 mm GI mm with 25x25x3mm angle stiffener
11	Surface finish	Powder coated
12	Drive Unit & Mounting Type	Motor - InDirect Mounting, Jielong Make

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry	In Client Scope
5	All structure support required	In NIHVA Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables considered upto control box	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment **: Supply :** 40% Advance along with Confirmed Purchase Order & 60% against material supply
: Installation : 100% immediate against installation

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd