**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**BR POWER CONTROL & AUTOMATION SERVICES**
Plot No.15, Krishana Industrial Area, Gali No 5, Sector 25,
Faridabad(Haryana) 121004 India

**Date :** 29.04.2021
**Quote NO :** **MHE_21.22.0006**
**Kind Attn :** Mr. Rajesh Sharma
**Email Id :** brpowercontrol@yahoo.com
**Contact No:** 9811323296

**Project Name & Location: Telescopic Truck Loader/Unloader Conveyor, Faridabad**

**Subject : Quotation for Telescopic Truck Loader/Unloader Conveyor**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 2 |
| D. | Terms & Conditions | 2 |

**A) Commercial Offer**

| Sr No | Description | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|
| | | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Telescopic Truck Loader/Unloader Conveyor** | **2** | **12,75,000** | **25,50,000** | **35,000** | **70,000** |
| | | **Total** | | **25,50,000** | | **70,000** |
| | P&F Charges | 3% | | **76,500** | | |
| | Total Without Taxes | | | **26,26,500** | | **70,000** |
| | GST Extra @ 18% | 18% | | **4,72,770** | | **12,600** |
| | Total With Taxes | | | **30,99,270** | | **82,600** |
| 2 | Transportation Charges | | | **Extra At Actual** | | |
| 3 | Unloading Charges @ Site | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Telescopic Truck Loader/Unloader Conveyor**

| Sr. No. | Parameters | Specification |
|---|---|---|
| 1 | Material to be conveyed | Bags OR Cartons Boxes |
| 2 | Maximum Product Size (L x W x H) | 600 X 500 X 400 mm |
| 3 | Maximum Weight | 50 Kg |
| 4 | Material Handling Rate | Upto 3000 bags or boxes Per Hour |
| 5 | Base Section Length(Retractable) | 4000 mm |
| 6 | Extension | 6000 mm |
| 7 | Total Length | 10,000 mm |
| 8 | No. of Extension Stages | 3 |
| 9 | Basic Overall Height | 900 mm |
| 10 | Belt Width | 600 mm |
| 11 | Belt Type | PVC 70 Sh.A/Smooth/Black/LF/Ldb Fabric/2 Ply/3.00 mm/SS/Fastener |
| 12 | Belt Speed | 25 - 45 mtr/min Variable through VFD, connecting to existing TLX |
| 13 | Belt Direction | Bi-directional for loading and unloading |
| 14 | Belt Drive | As per Design |
| 15 | Telescopi Movement Drive | As per Design |
| 16 | Power Supply | 240 VAC, 50 Hz |
| 17 | Load Capacity | 50 Kg/mtr |
| 18 | Finish | RAL 5002 ultramarine blue or as per client's request Base coat of Zinc Chromate Primer 2 coats of finish paint |
| 19 | Structure Construction | MS Heavy Duty Plates |
| 20 | Conveyor Mounting | Adjustable Levelling Mounts with grouting holes |
| 21 | Hydralic Lift | Upto 2500 mm from ground level |

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**D) Terms & Conditions**

**Price** : Ex Works Pune.

**Delivery** : 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation.

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd