NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Corning Optical Communications
Pune

Date : 24.04.2021
Quote NO : SQT.21.22.0043
Kind Attn : Mr. Abhijit Kulkarni
Email Id : KulkarniAA@corning.com
Contact No: 8308804379

Project Name & Location : Automatic Boom Barrier, Chakan Pune

Subject : Quotation for Boom Barrier

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**AUTOMATIC BOOM BARRIER** Length 4 mtr Key selector in case of Power Failure	4000	2	65,000	1,30,000	15,000	30,000
2	Sinlge Push Button		2	2,500	5,000		
3	Remote Control		2	3,500	7,000		
4	MS Resting Stand		2	3,850	7,700		
5	Pair of Safety Photocell Sensor		2	4,800	9,600		
6	Blinker With Antenna Swing/ Sliding Gate		2	3,800	7,600		
7	Double Channel Loop Detector		2	21,000	42,000		
8	LED Strip 5 Mtr Long		1	Not recommended			
9	Flashing Light with Buzzer		1	Not required, Blinker already considered			
		Total Amount			**2,08,900**		**30,000**
		P&F Charges	3%		6,267		
		Total Without Taxes			**2,15,167**		**30,000**
		GST Extra @ 18%	18%		38,730		5,400
		Total With Taxes			**2,53,897**		**35,400**
10	Transportation Charges						**Extra at actual**
11	Unloading Charges @ Site						**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specifications

Automatic Boom Barrier

Sr. No.	Description	Specification
1	Size	Upto 6 mtr
2	Make	BFT
3	Opening time	Opening Time- 6S/4S
4	Motor Power Supply	24 V
5	Limit devices	Electrical incorporated and electronically adjustable
6	Safety	Photocell sensor
7	Operated	Push Button Pedant
8	Operatin Voltage	230 V
9	Manual mechanical release	Key
10	Maximum Torque	600 Nm
11	Working temperature	from -20°C to +55°C
12	Internal lubrication	Permanent Grease
13	Protection Degree	IP54

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope
8	Lifting Equipements	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery :6- 8 weeks from confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Ravindra Kharat on 7410169333**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd