NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Rohan Builders (India) Pvt.Ltd.
1 Modibaug,Commercial Building,
Ganeshkhind Road,
Shivaji Nagar, Pune - 411 016.
Maharashtra, India.

Date : 06.02.2020
Quote NO : SQT/19-20/2404
Kind Attn : Rajan Khadloya
Email Id : bdm.pn@rohanbuilders.com
Contact No: 9665055181

Subject : Quotation for Rolling Shutter, Fire Rated Rolling Shutter , Sectional Door , High Speed Door and Dock Leveller. (Project -Procter & Gamble)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Sectional Door**	2400	3000	4	252,000	1,008,000	20,000	80,000
2	**Motorized Rolling Shutter**	3000	4000	2	105,000	210,000	20,000	40,000
3	**Motorized Rolling Shutter**	4000	4500	4	141,000	564,000	20,000	80,000
4	**Motorized Rolling Shutter**	3000	4500	2	111,000	222,000	20,000	40,000
5	**High Speed Door RR300+Alu**	3000	3000	20	717,000	14,340,000	20,000	400,000
6	**High Speed Door RR300+Alu**	3000	4500	2	756,000	1,512,000	20,000	40,000
7	**High Speed Door RR300+Alu**	4400	3000	2	755,000	1,510,000	20,000	40,000
8	**High Speed Door RR300+Alu**	3000	5000	2	777,000	1,554,000	20,000	40,000
9	**Fire Rated Rolling Shutter 2 Hrs**	3000	3000	4	217,000	868,000	20,000	80,000
10	**Fire Rated Rolling Shutter 2 Hrs**	3000	4500	2	275,000	550,000	20,000	40,000
11	**Fire Rated Rolling Shutter 2 Hrs**	3000	5000	2	327,000	654,000	20,000	40,000
12	**Fire Rated Rolling Shutter 4 Hrs**	3000	4500	1	268,000	268,000	20,000	20,000
13	**Fire Rated Rolling Shutter 4 Hrs**	44000	3000	1	269,000	269,000	20,000	20,000
14	**Fire Rated Rolling Shutter 4 Hrs**	3000	3000	6	248,000	1,488,000	20,000	120,000
15	**Dock Leveller 6 Ton**	2250	2500	1	220,000	220,000	15,000	15,000
16	**Dock Shelter**	3400	3600	1	150,000	150,000	15,000	15,000
				Total		**25,387,000**		**1,110,000**
17			P&F Charges	3%		761,610		
			Total Without Taxes			26,148,610		1,110,000
			GST Extra @ 18%	18%		4,706,749.80		199,800
			Total With Taxes			**30,855,360**		**1,309,800**
18			Transportation Charges			In Client Scope		
19			Unloading Charges @ Site			In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification **MS Motorized Rolling Shutter**

Sr .No.	Specification	MS Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75 mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Hand Crank

Technical Specification **Dock Leveller**

Description	Specifications
Capacity	10 Ton
Dock operation mode	AC power pack hydraulically operated
Lip operation mode	Hydraulic
Operation control	Through panel
Loading platform height from road	1250mm
Travel above & below dock level	(+) 300 / (-) 250 mm
Platform Size (W x L)	2250 mm x 2500 mm
Lip size (W x L)	2250 x 400 mm
Shut Height	480 mm
Overall length	2250 mm x 2500 mm + Lip Length (400mm)
Maximum slope can be achieved	10%
Clear Pit dimensions (W x L x D)	(W) 2300mm x (L) 2550 mm x (D)485 mm
Hydraulic power pack	Standard
Driver type	Direct by electric Motor
Motor Ratings	1 H.P
Pump design flow	2.5 LPM
Pump pressure	120 bar Operating 200 bar Max.
Safety valve set pressure	120 Kg/cm²
Pump Type	Gear
Volume of oil receiver	7 Lit
No Of Deck cylinder	2 No
Lip Cylinder	1 No
Dock Bumper	Pair of Dock Bumper

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Technical Specification **Sectional Door**

Sr .No.	Specification	Sectional Door -Crawford - NIHVA Assaabloy	
1	**Door produced Based on which certificatio**	Doors produced according to ISO 9000 or ISO 14000	
2	**Opening/Closing Speed**	0.25 m/s	
3	**Door Material**	GI Steel with PUF inside	
4	**Panel Thickness**	42mm	
5	**Panel colour**	RAL 9002 Powder coated	
6	**External surface of the panel**	diamond grid design with a glossy finish at the section	
7	**inside surface of the panel**	Monolithic surface on the inside of the door	
8	**Broken cold bridge**	Section joints with broken cold bridges	
9	**Door sealent**	All door sealants made of EPDM rubber.	
10	**All Panel height**	All panels should be 545mm high	
11	**Panel Inside insulation metrial**	Insulation material to be CFC free polyuretane foam.	
12	**Panel Flame Retardent standrad**	Flame retardant polyurethane foam according DIN4102-class B2.	
13	**Steel component Material**	All steel components to be electro galvanized	
14	**Hinge Material**	Glass fibre reinforced Polyamide	
15	**Panel Thickness**	42 mm	
16	**Spring Material surface finish**	Powder coated	
17	**Water Penetration**	EN 12425	class 3
18	**Air Permealibity**	EN12426	class 2
19	**Wind Load**	EN21424	class 3
20	**Thermal Transittance**	EN 12428 1.10W /m2K	
21	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber	
22	**Door saftey device 1**	Doors equiped with spring break device	
23	**Door saftey device 2**	Door equiped with pneumatic safety edge	
24	**Door saftey 3**	Having hinges flush with the inside door surface is a safety feature that eliminates the risk of things or people getting caught by parts protuding from a moving door	
25	**Incase of Power failuer**	One can operate the Door manually	
26	**Operator power conumption**	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W	
27	**Drive Unit & Mounting Type**	Single phase 230V direct drive on shaft	
28	**Emergency Operation**	by Disengagement rope manual	
29	**Operating Switch**	Up/Down Keypad + stopbutton	
30	**Environmental Green Product Declaration Certification**	as per ISO 14025 and EN 15804	

Technical Specification **Fire Rated Rolling Shutter**

Sr .No.	Specification	Fire Rated Rolling Shutter
1	**Shutter Curtain**	Single Skin Design
2	**Guide Rail**	Model : SKB-G65 powder coated
3	**Bottom Bar**	Model : SKB-T120 powder coated
4	**Type of Mounting**	Standard
5	**Motor Drive Unit**	Power Source: 110v 60Hz 1 phase 220v 6OHz 1 phase 230v 50Hz 1 phase 400v 50Hz 3 phase Insulation Class E Manual Chain Override One unit push button switch Gravity drop level Auto close by relay switch after receive of 24vdc fire signal

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 11 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain on (855) 109-2333** for any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd