NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Fresenius Kabi India Private Limited
Plot No-1,Phase-III,Honda Industrial Estate,
Honda Sattari, Goa - 403530, India

Date : **10.10.2019**
Quote NO : **SQT.19.20.2145**
Kind Attn : **Mr. Swapnil Desai**
Email Id : Swapnil.Desai@fresenius-kabi.com
Contact No: **8326733600**

Subject : Quotation for High Speed Door HS9020GAT, HS 9020G Clean Room Door & Sliding Glass Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Albany Make Rapid Roll Up Door HS9020GAT	1810	2050	1	4,82,000	4,82,000	20,000	20,000
2	Albany Make Rapid Roll Up Door HS9020GAT	2600	2040	1	5,29,000	5,29,000	20,000	20,000
3	Albany Make Rapid Roll Up Door HS9020GAT	1920	2040	2	4,83,000	9,66,000	20,000	40,000
4	Albany Make Rapid Roll Up Door HS9020G	1810	2050	1	4,37,000	4,37,000	20,000	20,000
5	Albany Make Rapid Roll Up Door HS9020G	2600	2040	1	4,80,000	4,80,000	20,000	20,000
6	Albany Make Rapid Roll Up Door HS9020G	1920	2040	2	4,38,000	8,76,000	20,000	40,000
7	Besam Sliding Glass Door	1100	2000	1	2,48,000	2,48,000	20,000	20,000
8	Automatic Swing Door	1100	2000	1	2,60,000	2,60,000	15,000	15,000
				Total		**42,78,000**		**1,95,000**
4	P&F Charges			3%		**1,28,340**		
	Total Without Taxes					**44,06,340**		**1,95,000**
	GST Extra @ 18%			18%		7,93,141		35,100
	Total With Taxes					**51,99,481**		**2,30,100**
5	Transportation Charges					**In Client Scope**		
6	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA ASSA ABLOY - Albany Make HS9020GAT



Sr. No	Description	Specifications
1	Door Type	The HS9020GAT is a compact, airtight door with integrated motor for inside environments, type clean room
2	Door Construction	Door Constrcution in Stainless Steel 304
2	Sealing	Unique side column technology provides excellent seal on all 4 sides thereby reducing heat loss.
3	Opening & Closing Speed	Opening: up to 1.2 m/s, Closing: 0.5 m/s
4	Safety features:	• Photocells in side columns, • Flexible door curtain without ridged parts • Flexible soft bottom edge including wireless edge activator • Break-away and self-repair function.
5	Vision Window	Single row with 400 mm Height
6	Wind load resistance	Class 1 (300 Pa (N/m²)) maximum wind load while closing 50 Pa (N/m²)
7	Water penetration	Class 2 (50 Pa (N/m²)
8	Air permeability	• Class 3 - Over Pressure • Class 1 - Under Pressure
9	Thermal transmittance	6,02 W/(m²K)
10	Lifetime expectations	1,000,000 cycles
11	Radar Sensor	On Both Sides

ASSA ABLOY Make Rapid Roll Up Door HS9020G **(Supply + Installation + Interlocking between two doors)**
• The HS9020G high speed door is designed for interior applications.
• Gravity drive system
• Unique side column technology provides excellent seal on all 4 sides thereby reducing heat loss.
• The speed of opening is up to up to 1,2 m/s depending on size of door.
• The speed of closing is 0,5 m/s
• The door design withstands overpressure or underpressure in specific areas
• Photocells in side columns.
• Wind load resistance: (EN 12424) Class 1 (300 Pa (N/m²)). Maximum wind load while closing 50 Pa (N/m²)
• Water penetration (EN 12425) Class 2 (50 Pa (N/m²)) 20 minutes water spray
• Air permeability (EN 12426) Class 1 (24 m³/m²/h at 50 Pa)
• Thermal transmittance (EN 12428) 6,02 W/(m²K)
• Temperature working range: 5 °C to +40 °C
• Door curtain 900 g/m² colored PVC, material thickness: 0,8 mm
• Flexible door curtain without ridged parts.
• Flexible soft bottom edge including wireless edge activator.
• Break-away and self-repair function.
• The door curtain is available in 8 standard colors.
• Various window - 400 mm height single row.
• The motor with frequency converter guarantees smooth and reliable operation.
• Soft start/stop significantly prolongs motor lifespan.
• Operator 220V - 240V 1-phase 0,75 kW 16A
• Operator protection: IP65
• Control unit with display, impulse Up and Down buttons, an emergency stop mushroom button and a mechanical main switch.
• Control unit protection: IP54
• Lifetime expectations: 1.000.000 cycles

Sliding Glass Door
ASSA ABLOY-BESAM-Automatic Sliding Door SL 500
100% imported from Sweden
Specifications :
1. Main power supply
2. Operator type- Bi part operator.
3.Glass : 10mm thick toughened glass

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 12-13 Weeks for High Speed Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Swapnil Kulat on 7219207333**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd