BOQ

Name of Contractor : Nihva Technologics Pvt Ltd

Date: 01.12.2025

Name of Work:- Replacement of dome double wall sheet with new polycarbonate sheet at FID, ARAI, Chakan, Pune.

Sr. No.	Description of Item	Unit	Qty.	Rate	Amount
1	**Replacement of existing dome double wall sheet with providing and fixing 3mm solid Polycarbonate sheet** (Make: Palaram, Lexan, Palsun, Tllara, Durotuff, PC Lite or equivalent-**10 year warranty**) Including installation **over existing MS frame structure** including all accessories required for installation- Powder coated Aluminium Profile, EPDM, weatherseal Seleant etc all complete. Approx. Size is as per drawing attached. **(Scope also include removing and disposal of existing dome double wall sheet outside ARAI premises)**. Polycarbonate colour shed as per ARAI Engineer-In charge directions.	Nos	1.00	491700	491700
	Total Basic Amount				491700/-
	Add CGST 9%				44253/-
	Add CGST 9%				44253/-
	Total Amount				580206/-

Special Note : Please follow all safety norms and provided all necessary safety PPE to Workers while execution as per type of work.

NIHVA TECHNOLOGIES PVT. LTD. PUNE

Authorised Signature & Stamp