NIHVA
NIHVA Technologies Pvt. Ltd.

Quotation reference: **SQT/19-20/1551** **Date: 04th June 2019**

Afcons Infrastructure Ltd
Veera Desai Road,
Andheri (W), Mumbai-53

Kind Attn: Mr. Bhushan
Contact No: 022 67191 189
Email ID: bhushan.deshmukh@afcons.com

Project Location : **Mauritius Island**

Subject : Supply & Installation of Sliding Hangar Door (Commercial Offer)

PRICING –

Supply Price includes Custom Duty, custom clearance:

Sr no	Description	Price/Each in Rs	Qty No	Total Price in INR
Hanger Door: Size – (W) 51 Mtr x (H) 14 Mtr				
1	supply of Automatic Double leaf Telescopic Sliding Hangar doors - Ex Mumbai Nahava sheva sea port	68,500,000	1	**68,500,000**
2	Installation & Commissioning	9,000,000	1	**9,000,000**
3	Lifting equipments (details mentioned below)			**Client scope**
4	New Steel structure construction with design for above sliding door			**Client scope**
5	Civil work for bottom track and if any other			**Client scope**
		Total		**77,500,000**

Lifting Equipment

Unloading of containers will require a 25T Crane, there is likely to be 4 separate containers, therefore 6 days

Assemble of door leaves and moving of materials around the site will require a 2.5 Tonne straight mast fork lift truck – 9 weeks

Lifting of door leaves will require 2No. approx.. 50 - 70 tonne capacity cranes. We can will lift 2 door leaves per day, therefore require the 2 cranes for two weeks.

For installing top guide tracks, lifting doors, M&E, Cladding etc we will require a 15m working height scissor lift for up to 9 weeks

Note :

Please note that we have included for the door leaves to open into enclosed door pockets, not open into 'sturdy outriggers'. The door leaves are power operated but work in two halves as sheaved door leaves. They are not individually power operated.

Terms & Conditions:

Payment : 50% along with confirmed purchase order & balance 50% irrevocable LC along with Purchase order & will be discharge before material handover at NAHA SHEVA SEA Port Mumbai.

P & F Charges : @3% of total supply value

GST : Extra 18%

Validity : 15 days from the date of offer

Delivery : 20 to 22 weeks from the date of receipt of confirmed order, drawing approval.

Installation : 90 Days Uninterupted continuous working days , if our installation work stops because of any reason the idle time/Days will be charged extra

Insurance : Extra as applicable

Warranty :12 months from date of Supply

Compensation clause : Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA a compensation of 25% of order value.

General conditions of Aircraft Hangar Door

- Continuous uninterrupted access to any single door section or as agreed separately.
- 400 volt / 50Hz 3 phase isolator to be fitted to within 1 mtr of the door main control panel. If not available at the start of installation, a temporary supply is acceptable. Any return visits to commission the doors due to permanent power not being available will be charged as appropriate.
- Provision of 230 Volt power supply (by others) for hand tools.
- A dry & secure area, not in direct sunlight, is to be provided for storage of the door components.
- Access to site between 7 am to 6 pm six days per week. If this is not possible the installation programme may require amending.
- The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practices. We reserve the right to extend the period accordingly.
- Any passes, Lodging & Boarding (Accomodation & Food) Sea Travelling (MUMBAI to Mauritius & back to Mumbai) required for the project, are the responsibility of the Customer, before commencement of the installation.

Inclusions

- A pre-installation inspection will be carried out, by our Project Manager, before our installers travel to site, so as to verify that the structural steelwork and electrical installation are as per our requirements. Our Project Manager will also check that the installation equipment and facilities are ready for installers.

Exclusions

The following items are not within our scope of works and are to be provided by others at no cost to NIHVA.

- All cladding sheets and flashings required for the doors will be provided by Client.
- Any other metal wall panels and associated flashings, fixings and like materials required for sheeting the doors are excluded from our supply.
- All steelwork for connecting our top tracks to, are excluded from our supply.
- Provision of suitable mounting points for various items e.g. jamb seals, sheaving system connections points etc. are excluded from our supply.
- Additional painting, other than specified above, is excluded from our supply.
- Additional design modifications and materials are excluded from this offer.

Please feel free to Contact Mr. Arjun Patil on 08551096333 For any further Clarification /Information in this Concern.