NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Lupin
PUNE

Date : 15.03.2021
Quote NO : SQT.20.21.3101
Kind Attn : Mr. Dheeraj Sawant
Email Id : dheerajsawant@lupin.com
Contact No: 9833273706

Subject : Quotation for Telescopic Motorised Gate & Tripod turnstile .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Three Leaf Telescopic Motorised Gate .**	4740	2400	1	4,78,000	4,78,000	20,000	20,000
2	**Single Lane Half Height Turnstile Gate: SS 304** • It has zero position of self -checking, easy for users to maintain and use. • Alaram Function for Unautorised Access • Avoid bump funtion • IR/mechanical dual anti-lined funtion • Reseng automatically • Standard wiring connection • The whole system works steadily, and the noise is very low. Unlock time: 0.2s Pass rate: 35 person/min Pass Width: 550mm ; Input: 100V~240V; Driving Voltage: 24v; Environment: -20~60°c; Power Consumption: 35w Weight: 45kg	280	980	3	67,500	2,02,500	15,000	45,000
3	Controller for entrance system with SMPS power supply			3	22,500	67,500		
4	HID Card Reader			6	8,500	51,000		
5	HID Card			100	185	18,500		
6	Windows base Software with IN-OUT entry			1	10,000	10,000		
7	Integration with Existing Software			1	Client Scope	Client scope		
				Total		**8,27,500**		**65,000**
				P&F Charges	3%	24,825		
				Total Without Taxes		8,52,325		65,000
				GST Extra @ 18%	18%	1,53,418.50		11,700
				Total With Taxes		**10,05,744**		**76,700**
				Transportation Charges				**Extra at actual**
				Unloading Charges @ Site				**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Three Leaf Telescopic Motorised Gate

Sr .No.	Specification	Telescopic Sliding Gate
1	**Door type**	Motorised Three Leaf Telescopic Sliding Gate
2	**Master Leaf Size**	1580 X 2400 mm
3	**1 ST Leaf Size**	1580 X 2400 mm
4	**2 ST Leaf Size**	1580 X 2400 mm
5	**Opening Direction**	Horizontal - from left to right or reverse
6	**Mounting Location area**	Inside area
7	**Design Pattern**	Standard Tubular Design Pattern
8	**Outer Frame Tube Sizes**	80x80x3.2 MM THK SQ. TUBE
9	**Internal Vertical Tube Sizes**	40x40x2.6 MM THK SQ. TUBE
10	**For Post**	80x80x3.2 MM THK SQ. TUBE
11	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
12	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings
13	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
14	**Painting**	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
15	**Control Panel**	2 Nos Operating Station.(Motor Panel and Security Room)
16	**Operation**	By Telescopic Mechanism
17	**Accessories**	1. Limit Switch for Cut out when Gate is fully Closed
		2. Flashing Light
		3. Hooter
		4. Photocell

Motorised Half Height Trunstile

Sr .No.	Description	Specifications
1	**Framework**	**304 SS**
2	**Finishing**	**Brushed**
3	**Dimension L X B X H**	**480 x 280 x 980 mm**
4	**Pass Width**	**550 mm**
5	**Pass Rate**	**35persons/min**
6	**Operation**	**Single/Bi-directional**
7	**Rotor Type**	**3 arm x 120°**
8	**Mechanism**	**Electro-Mechanical**
9	**Locking**	**25° from previous rest position**
10	**Power Voltage**	**AC 220V +/- 10% 50-60Hz**
11	**Power Consumption**	**80W per lane**
12	**Mode**	**Fail Safe**
13	**Operating Temprature**	**-20°C - 55°C**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 07410169333** For any further Clarification /Information in this Concern.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd