NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

RMK Infrastructure Pvt. Ltd.
Talegaon
Maharashtra -India.

Date : 26.05.2020
Quote NO : SQT.19-20_2538
Kind Attn : Mr. Nisar Magdum
Email Id : nisar.magdum@rmkinfrastructure.com
Contact No:

Project Name & Location: HIRANANDANI PARKS, Pune

Subject : Quotation for Sectional Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Automatic Sectional door - Vertical Lift**	2400	3000	4	2,23,000	8,92,000	inclusive	
				Total		**8,92,000**		-
			P&F Charges	3%		**26,760**		
			Total Without Taxes			**9,18,760**		-
			GST Extra @ 18%	18%		1,65,377		
			Total With Taxes			**10,84,137**		-
			Transportation Charges			**Extra at Actual**		
			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sectional Door (ASSA ABLOY)

Sr. No	Description	Specification
1	Model No	ASSA ABLOY OH1042P
2	Opening Direction & Mounting	Vertical
4	Opening/Closing Speed	CDM9 0,28 m/s
5	Door Material	GI Steel
6	Panel Thickness	42 mm Square Grid, steel sheet
7	Filling	CFC-free polyurethane
8	Door sealent	All door sealants made of EPDM rubber, temperature resistant -30/+70
9	Water Penetration	EN 12425 class 3
10	Air Permealibity	EN12426 class 3
11	Thermal Transittance	EN 12428 1.10W /m2K
12	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
13	Door saftey	Doors equiped with spring break device
14	Incase of Power failuer	Doors to be equiped with quick release fuction
15	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
16	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
17	Emergency Operation	by Disengagement rope manual
18	Operating Switch	Up/Down Keypad + stopbutton
19	Locks : Lock bolt	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
20	Environmental Green Product Declaration Certification	As per ISO 14025 and EN 15804

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	NIHVA Scope
4	All structure support required	In Client Scope
5	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
6	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Site

Delivery : 5-6 weeks for Rolling Shutter, 12 -14 weeks for Sectional Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd