NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Rane Engine Valve Ltd
Survey No : 177/20, AZIZ NAGAR
Moinabad Mandal,
RR Dist -Hyderabad - 500 075

Date : 27.08.2019
Quote NO : SQT.19.20.1974
Kind Attn : Mr. Ramesh.T
Email Id : tr.ramesh@ranegroup.com
Contact No: 7032 1 88825

Project Name & Location: Hyderabad .

Subject : Quotation for Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Floor Mounted Scissor Lift**	1200	600	1	225,000	225,000	NA	NA
				Total		**225,000**		
2	P&F Charges			3%		**6,750**		
	Total Without Taxes					**231,750**		
	GST Extra @ 18%			18%		41,715		-
	Total With Taxes					**273,465**		**-**
3	Transportation Charges					**In Client Scope**		
4	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Floor Mounted Scissor Lift

Sr. No	Description	Specifications For 6 Ton
1	Capacity :	200 kgs
2	Platform size :	1200L x 600W
3	Shut ht :	350 mm
4	Open ht :	1800 mm
5	Power pack :	1 HP, 3 PH
6	Hydraulic lip	350 x 5 x 1200
7	Color :	as per req.
8	Roller platform	OD 42 x 500L = 15 nos (with plating)
	Safety parameters :	
1	Pilot operated check valve.	
2	Buzzer while operation UP & DOWN.	
3	Max ht limit switch.	
4	Over load relay.	

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Swapnik kulat on 7219207333.**

With Best Regards
Ulka Auti.
7219206333
For NIHVA Technologies Pvt Ltd