Qualites Infrastrukture

WORK ORDER

To, NIHVA Technologies Pvt. Ltd., Thremax Chowk M.I.D.C. Chinhwad, Pune – 19 GST No: Kind Attn. – Mr. Ravindra Kharat Mobile – 7410169333 Project Name & Location: Tenneco Air India Pvt Ltd	W.O. No. : QI/PO/TEN/01/2020-21(old W. No.BASB/PO/SPL/8/2020-21) Date : 25/8/2020 Reference : Ref Date : GST No. : 27AETPG9518E2Z4 PAN NO : AETPG9518E

Sr. No	Description	Size		Qty	Supply Charges in INR	Installation Charges in INR	
	Supply & Fixing	Clear Width	Clear Length	(Nos)	Unit Price	Unit Price	Total Amount
		(mm)	(mm)				
1	Motorised Rolling Shutter	2400	4000	1	80000	15000	95000
2	Motorised Rolling Shutter	4500	4000	1	127000	15000	142000
	P& F Charges						
	Total Without Taxes				207000	30000	237000
	Gst Extra @18%						42660
	Total With Taxes						279660
	Transportation Charges						NILL

B) Technical Specification

NIHVA Rolling Shutter

Sr. No	Description	Specifications
1	Rolling Shutter	Motorised Rolling Shutter with mild steel of Thickness of 1 mm
2	Mounting Location area	Inside area
3	Curtain Panel	The panel made of 1 .0mm thick MS steel
4	Curtain Panel Size	75mm wide
5	Curtain Profile	Curved
6	Bottom Profile	M.S. Plate 100 mm x 2.5 mm thick with angle stiffener
7	Side Guide Profile	M.S."U" Shaped profile 65 mm -150 mm x 3 mm thick (as per te opening dimension)
8	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia -100 to 300 mm as per w x h
9	Side Brackets	M.S Plate 3 mm to 10 mm thick, as per the opening dimension
10	Hood Cover	Made Of GI sheet Thickness 0.9 mm GI mm with 25x25x3mm angle stiffener
11	Surface Finish	Powder coated
12	Drive Unit & Mounting Type	Electric Motor- Indirect Mounting

C) General Specifications

1. You will mobilize the installation Team in 2 -4 working days, after receipt of all material at site
2. If Lifting Equipment's are in NIHVA Scope, then those will be used installation purpose only

Sr. No.	Description	Remark
1	Scaffolding/Hydra/Crane/Forklift etc-required for Installation At Site	By QI
2	Electrical Supply on the site single phase/three phase at one place.	BY QI
3	Any Civil/ masonry /structural work required	BY QI
4	All Structure support required	BY QI
5	Conduits, Cables if required	BY QI

D) Terms & Conditions

Price	Works Pune
Transportation	NIVHA SCOPE
Delivery	1 Weeks from the date of receipt of confirmed purchase order, Advance Payment & drawing approval (Already Paid Rs 50000/- on date 16/03/20)
Payment	i) Rs 50000/- Advance paid ii) Rs 2 Lacs immediate after receipt of material at site and inspection and before installation iii) Rs 29660 immediate after commissioning, testing and installation.
Warranty	12 months from the date of a satisfactory completion certificate from client

With Best Regards,

Bibhishan P Ovhal
For Qualites Infrastrukture