NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0103 **Date : 20-03-2018**

ACME Cleantech Solutions Pvt Ltd
Plot No.: 3-8 & 29-34, Sector-5 IIE Sidcul,
Pantnagar-263153 (UK) India

Kind Attn : **Pushpendra kumar**
Email : pushpendra.kumar@acme.in
Contact No : 9149079600

Subject : Quotation for Manipulator with Gripper

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

A	**Floor mounted Manipulator**
	Manipulator : 1. Manipulator enables the safe and efficient handling of many products up to a maximum weight of 200 kg. 2. Manipulator incorporates a pneumatic cylinder to achieve the lifting action, and is normally custom built to suit the relevant working environment 3. Low noise levels and low maintenance make manipulator the ideal solution for your material handling problems 4. Three control styles ensure maximum flexibility. Auto balance, powered lift/lower, and pre-set loaded/unloaded options allow the most suitable control style to be used for each handling application
	

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
1	**Power Electronics (Box) Assembly Manipulator**				
	A. Manipulator	1	No.s	6,70,000.00	6,70,000.00
	B. Gripper	1	No.s	6,30,000.00	6,30,000.00
	Total				**13,00,000.00**
2	**Front Seat Manipulator**				
	A. Manipulator	1	No.s	6,70,000.00	6,70,000.00
	B. Gripper	1	No.s	7,10,000.00	7,10,000.00
	Total				**13,80,000.00**
3	**Rear Seat Manipulators**				
	A. Manipulator	1	No.s	6,70,000.00	6,70,000.00
	B. Gripper	1	No.s	7,10,000.00	7,10,000.00
	Total				**13,80,000.00**
4	**Door Assembly Manipulators**				
	A. Manipulator	1	No.s	6,70,000.00	6,70,000.00
	B. Gripper	1	No.s	6,30,000.00	6,30,000.00
	Total				**13,00,000.00**

5	**IP (Dashboard) Instrumental Panel Manipulators**				
	A. Manipulator	1	No.s	6,70,000.00	6,70,000.00
	B. Gripper	1	No.s	6,30,000.00	6,30,000.00
	Total				**13,00,000.00**

6	**Air Booster & filter**	**1**	No.s	1,30,000.00	**1,30,000.00**

Note : 1. Gripper price may be vary as per structure & drawing provided by client
2. Installation value is 10% of supply value for each.

Technical Specifications :

Sr. No.	Specifications	Details
1	Weight range of the Component(Min-max)	35 kg for Door Assembly, IP (Dashboard) Instrumental Panel, Rare seat & front Seat Manipulator and 100kg for Power Electronic Assembly
2	No. of variants	3 variants
3	4 Picking positions/ Locations of the component 300 mm from the ground With the respective heights	300 mm from the ground
4	5 Placing positions/ Locations of the component Inside the car – 700mm from the ground With the respective heights	Inside the car – 700mm from the ground
5	6 Max. distance between picking & Placing 2 mtrs. Position	2 mtrs
6	Orientation/ tilting after picking, if any	Tilting to be consider while insertion
7	Snaps & drawing. (2D & 3D) of the component	--
8	Preferred Configuration Column mounted/ Rail mounted option in case of manipulator/Air balancer	9 Preferred Configuration Column mounted/ Rail mounted option in case of manipulator/Air balancer Floor mounted, other will be Depending on manipulator design
9	Height of Supporting Structure Available for rail mounted system	10 Height of Supporting Structure Available for rail mounted system 3.5 mtrs.
10	Air pressure available (In Bar)	5-6 bar
11	Quality of Air (2-3 Degree Dew Point, Dry air)	Yes, available
12	Cycle time	3 minutes
13	Layout constraint if any	No
14	15 Work station/ Picking/ Placing Position Conveyor line (Mobile or Stationary)	Conveyor line

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	Extra 3%
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	7-8 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% advance along with confirm Purchase Order & balance before dispatch
6	**Insurance**	:	Extra at actual
7	**GST**	:	Extra @ 18%
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Monika Kadam

7219207333

For Nihva Technologies Pvt Ltd