adani	STANDARD FIELD QUALITY PLAN									
	ITEM: Erection & Installation of Fire Rated & Flush Steel Doors					SFQP NO: ADANI / QA / SFQP / C / 45 REV.NO. 1 DATE: 03.05.2019 Page 1 of 7				Approved by QA
SL. NO	ACTIVITY/ OPERATION	CHARACTERISTICS	CLASS OF CHECK #	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD		REMARKS
1	2	3	4	5	6	7	8	9	D	10

IMPORTANT INSTRUCTIONS:-

1. Head FQA and head of executing dept at site shall ensure the following before start of civil work & periodically thereafter:-
   a) Setting of FQA lab by contractor with necessary & essential testing equipments in good working condition.
   b) Calibration of all measuring and testing equipments to be used by contractor.
   c) Deployment of contractor's FQA manpower with prior approval of client FQA.

2. Non-conformity:- in case of any non-conformity, site FQA shall ensure proper dispositioning and NC no. Shall be recorded in the respective log sheet/ protocol.

3. The contractor shall intimate concerned authority in writing well in advance as per procedure mutually agreed with site FQA & site execution for witnessing of class "a & b" checks identified in standard field quality plan.

4. Record of quality checks shall be maintained in enclosed formats to provide necessary evidence of having carried out the work satisfactorily. Wherever format is not identified, records shall be maintained in a mutually agreed format to record all checks and tests.

5. For checks where log sheet is not called for, record shall be maintained in a suitable protocol. The format of protocol shall be mutually agreed by head fqa and head of the executing dept. At site.

6. After completion of activity, the contractor shall submit records of quality documents (two sets of hard copy & one set of soft copy) as identified in standard field quality plan in column 'd'.

7. Contractor shall submit monthly schedule of tests to be carried out by 5th of every month.

8. This document should be read in conjunction with technical specification, construction drawing and bill of quantity.

9. It is necessary & essential to carry out surveillance checks of 20% of each item of check by authorized executives as identified in note 2 of FQP record shall be maintained.

adani	STANDARD FIELD QUALITY PLAN									
	ITEM: Erection & Installation of Fire Rated & Flush Steel Doors					SFQP NO: ADANI / QA / SFQP / C / 45 REV.NO. 1 DATE: 03.05.2019 Page 2 of 7				Approved by QA
SL. NO	ACTIVITY/ OPERATION	CHARACTERISTICS	CLASS OF CHECK #	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD		REMARKS
1	2	3	4	5	6	7	8	9	D	10

INDEX

SL. No	Description	Page No	SL. No	Description	Page No
A	Material Approval (Including Bought Out items)	3			
B	Erection & Installation of Fire & Flush Steel Doors	4			

adani	STANDARD FIELD QUALITY PLAN									Approved by QA
	ITEM: Erection & Installation of Fire Rated & Flush Steel Doors					SFQP NO: ADANI / QA / SFQP / C / 45 REV.NO. 1 DATE: 03.05.2019 Page 3 of 7				
SL. NO	ACTIVITY/ OPERATION	CHARACTERISTICS	CLASS OF CHECK #	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD		REMARKS
1	2	3	4	5	6	7	8	9	D	10

A. MATERIAL APPROVAL

adani	STANDARD FIELD QUALITY PLAN									
	ITEM: Erection & Installation of Fire Rated & Flush Steel Doors					SFQP NO: ADANI / QA / SFQP / C / 45 REV.NO. 1 DATE: 03.05.2019 Page 4 of 7				Approved by QA
SL. NO	ACTIVITY/ OPERATION	CHARACTERISTICS	CLASS OF CHECK #	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD		REMARKS
1	2	3	4	5	6	7	8	9	D	10
1.	Material Approval including Bought out Item	Submission of Sample for Material Approval	A	Physical / Documentation / Measurement	100%	Tech. Spec. / Appd. Drg.	**Note : A1**	QA –C / F – 37 & 38 R.0	✓	**Note A1 :-** **Approved by FQA based on following criteria.** • Requirements of Tech. Spec. / Appd. Drg. • Witness of Lab Test (if required). • Third Party Test Report. • Manufacturer's Test Certificate. • Material Data Sheet. Contractor has to ensure fulfillment of all requirements stipulated above & requirements raised by FQA for approval of Raw material as well as bought out items like Aggregates, Source of Brick, Stone & Concrete Blocks, admixture, grout, doors, windows, sanitation items, various type of pipes, protective coating, paint, putty etc.

adani	STANDARD FIELD QUALITY PLAN									
	ITEM: Erection & Installation of Fire Rated & Flush Steel Doors					SFQP NO: ADANI / QA / SFQP / C / 45 REV.NO. 1 DATE: 03.05.2019 Page 5 of 7				Approved by QA
SL. NO	ACTIVITY/ OPERATION	CHARACTERISTICS	CLASS OF CHECK #	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD		REMARKS
1	2	3	4	5	6	7	8	9	D	10
B. ERECTION AND INSTALLATION OF FIRE & FLUSH STEEL DOORS										
1	Receipt of Doors & Accessories at site.	Material Receipt Inspection.	B	Visual	100%	Tech. Spec. / BOQ	Doors & Accessories should be received at site in Undamaged condition.	SR		
2	Erection & Installation.	a) Check for Dimension	B	Measurement	100%	Tech. Spec. / BOQ	Tech. Spec. / BOQ	SR		
		b) Erection of Door Frame	B	--DO--	--DO--	--DO--	--DO--			
		c) Verticality & Alignment	B	Measurement	--DO--	--DO--	--DO--	SR		
		d) Workmanship	B	Visual	--DO--	--DO--	--DO--	SR		
		e) Cement Concrete Grouting in Door Frames.	B	Physical	--DO--	--DO--	Tech. Spec. / BOQ / Cement Concrete of Proportion 1:2:4 (1C : 2 S : 4 Agg)			
		f) Mastic Caulking	B	Visual	--DO--	--DO--	Tech. Spec. / BOQ			

adani	STANDARD FIELD QUALITY PLAN									Approved by QA
	ITEM: Erection & Installation of Fire Rated & Flush Steel Doors					SFQP NO: ADANI / QA / SFQP / C / 45 REV.NO. 1 DATE: 03.05.2019 Page 6 of 7				
SL. NO	ACTIVITY/ OPERATION	CHARACTERISTICS	CLASS OF CHECK #	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD		REMARKS
1	2	3	4	5	6	7	8	9	D	10
		g) Installation of Fire Rated / Flush Steel door shutter with SS Hinges.	B	Physical	--DO--	--DO--	--DO--			
		h) Fixing of Fire Rated / Flush Steel Door Accessories.	B	Physical	--DO--	--DO--	--DO--			
		i) Check smooth operation of door & shutter	B	Visual	--DO--	--DO--	--DO--	SR		
3	Post Installation Repairing Work	a) Repairing Work	B	Physical	--DO--	--DO--	--DO--			
		b) Final Touch up for Painting	B	Physical	--DO--	--DO--	--DO--			

LEGEND :-

1) D*: Records identified with 'TICK' (✓) shall essentially be included by Supplier in QA Documentation.

2) Legend used for Class of check are A, B & C

- 'A' class of check shall be witnessed by ADANI/FQA, Surveillance by Head ADANI (FQA)
- 'B' class of check shall be witnessed by ADANI'S Executing Dept and Surveillance by ADANI/ FQA Engineer
- 'C' class of check shall be witnessed by Contractor's FQA and Surveillance by Concerned Executing Engineer for the respective work package

Note:- 1)'A' and 'B' class of checks shall be Adani's Customer Hold Points to be witnessed and work shall not proceeded till it is witnessed and cleared by ADANI.

2) It is necessary and essential to carry out surveillance checks of minimum 20% of each class of check by the authority identified for surveillance check and suitable records/protocols shall be maintained.

Abbreviations to be used in column -9 of Standard Field Quality Plan:-

SR=Site Register, TR=Test Report, TC=Manufacturer's Test Certificate, LR=Lab Report, LB=Log Book. LS= Log sheet (specify the log sheet no.)

adani	STANDARD FIELD QUALITY PLAN									Approved by QA
	ITEM: Erection & Installation of Fire Rated & Flush Steel Doors					SFQP NO: ADANI / QA / SFQP / C / 45 REV.NO. 1 DATE: 03.05.2019 Page 7 of 7				
SL. NO	ACTIVITY/ OPERATION	CHARACTERISTICS	CLASS OF CHECK #	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD		REMARKS
1	2	3	4	5	6	7	8	9	D	10