NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Shah Constructions
Marketyard, Pune

Date : 01/10/2020
Quote NO : SQT.20.21.2672
Kind Attn : **Mr.Rajesh Shah**
Email Id : rps0305@gmail.com
Contact No: 9422026643

Subject : Quotation for Refurbishment of existing Hangar Door at Pune Airport- Qty- 6Nos

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification/scope of work	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer **Refurbishment and Automation of existing Hanger door(Dismantling, Reinstallation, Gear motor and other mechanical components , labor cost)**

						A		B		C	
Sr No	**Description**		**Size**		**Qty**	**Gear and motor Automation Charges in INR**		**Mechanical /Electrical Material Supply Charges in INR**		**Labour Charges for Dismentling, Repair, Refixing & Trials in INR**	
			Clear Width (mm)	**Clear Length (mm)**	**(Nos)**	**Unit Price**	**Total Amount**	**Unit Price**	**Total Amount**	**Unit Price**	**Total Amount**
1	P-165 Hanger		**62000**	**8500**	**2**	1,150,000	2,300,000	2,500,000	5,000,000	500,000	1,000,000
2	P-01 Hanger		**45000**	**9000**	**2**	1,150,000	2,300,000	2,250,000	4,500,000	500,000	1,000,000
3	P-70 Hanger		**30000**	**8500**	**2**	1,150,000	2,300,000	2,200,000	4,400,000	500,000	1,000,000
				Total			**6,900,000**		**13,900,000**		**3,000,000**
				Total Project cost Without P&F + Taxes	**A+B+C**						**23,800,000**
				P&F Charges	3%						**624,000**
				GST Extra @ 18%	18%						4,284,000
				Total Project cost With Taxes							**28,084,000**
				Transportation Charges							**Extra at Actual**
				Unloading Charges @ Site							**In Client Scope**

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Exclusions :

The following items are not within our scope of works and are to be provided by others at no cost to NIHVA

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation, loading and unloading work at Site whenever required
3	A 400/230 power supply (permanent or temporary) must be provided (FOC) by the main Contractor during the installation of the door for power tools and testing of the door sections during erection.
4	Any civil / masonry/structural work required, yellow mark Civil/flooring work or if any and supply and installation of Rails or track and related civil work
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduiting, Cables and Electrical Connection required at required points
8	Any type of PEB work and metal sheet supply and installation work
9	Any type of Painting and flooring work
10	If Any extra steel /channel required during repairing work for strenthening of door structure or door leaf will be at extra cost at actual
11	Any passes required for the project, are the responsibility of the Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.
12	Any type of third party Inspection and Certification work, which are not within our scope of works but may be required by the Consultant or Client, these will be carried out or provided, subject to the actual requirements but will be at additional cost (by main contractor).

NIHVA Scope Of Work :

1 **Dismantling of Hangar Door : Scope includes**

a) Dismantling , repair, rework and fabrication of existing door leaf
b) Mechanical fabrication and Machining as required
c) labor and manpower for the dismentling work
d) All the machines, electrical power tools required for repairing
e) All Design & Structural Drawing as specified in approved Drawing submitted by the contractor through approved Consulting Agency and as per direction of Garrison Engineer.
f) Supply and Installation of mechanical parts, metal wheels with Bearings and other mechanical components if any
g) Material & labour for re-installation of refurbish door
h) Supply & fix hanger door specification complete all as existing door and as per design

2 **Mechanical Repair and Reinstallation of Hangar Door : Scope includes**

a) Aligning of bottom tracks existing tracks, repair of ball bearing/ machining/ complete wheels necessary as required of all top and bottom wheel
b) Mechanical fabrication and Machining as required
c) labor and manpower for the dismentling work
d) All the machines, electrical power tools required for repairing
e) Supply and Installation of mechanical parts, metal wheels with Bearings and other mechanical components if any
f) Material & labour for re-installation of refurbish door,Re-assembling of wheels, placing ball bearing, re-fixing on door leafs etc complete all as specified and directed
g) Supply & fix hanger door specification complete all as existing door and as per design
h) Making all door leaf aligned and straight by taking down door leaf, with all alteration and of small sections all as required without adding any steel material , if steel material needed will be charges extra
i) Replacing of existing wheel with drive wheel, required two drive wheels for one opening, Drive wheel shall contain either gear on the flange portion or shall have chain sprocket arrangement as per OEM etc. complete all as specified and directed

3 **Automation of Hangar Door : Scope includes**

a) Providing & fixing 3-phase new motorization system with suitable capacity of motor, fixing on master door leafs only with all required cabling, conducting, and Limit switches.
b) The capacity of motor shall be minimum 3 H.P. The mode of operation shall be one master at each side
c) Providing and fixing outdoor type weather protected fully enclosed control panel with LED push button switches with function (Forward-Reverse-Stop) & Motor Protection, Overload protection, safety switches, Emergency Stop, Key Selectors.Audio/ Visual Alarm
d) Auto track cleaners to be fitted at bottom of all leafs and EPDM gasket at centre leaf
e) Festoon cable carrier arrangements, track cleaners, complete to work smoothly of existing manually sliding bi-parting hanger doors
f) Supply and Installation of mechanical parts, metal wheels with Bearings and other mechanical components if any
g) Providing of Idler braking system to be attached with motor gear system via chain sprocket assembly drive, conneters, EPDM Gaskets at centre leafs
h) Providing and fixing of Manual declutching system for any emergency at a suitable height by twisting the mechanism with Handle Shaped LN key
i) Replacing of existing wheel with drive wheel, required two drive wheels for one opening

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 1 week , after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

I. Preliminary schedule

The schedule below is preliminary. The schedule times will change subject to the final choice of door design. Critical milestones are receipt of the LPO, receipt of the advance payment, final approval of shop drawings, and successful load test of the building and overall site readiness for the door installation.

Delivery time: 25 days / door subject to complete clearnce from client, approval on drg and work method statement signed and stamp

Installation time is subject to site readiness, clear working area and delays by others. Detailed program will be agreed with our project coordinator.

II. Delivery conditions

1 Delivery of material will be coordinated with the client written construction schedule. The contractor is responsible for notification to Megadoor of any expected or actual delays in the agreed delivery date at least fourteen (14) days prior to the scheduled delivery.

2 Without timely notification of changes in delivery dates, the contractor or contractor's representative will assume the responsibility of unloading and storing the provided materials in a manner to prevent damage of the materials.

III. Drawings

We will issue a full set of shop drawings for approval within 2 weeks of receiving the confirmed order and finalized design details

IV. Compensation clause

Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA compensation of 25% of order value.

General Pre-Requisites Required at Site

Prerequisites:

1. Finished Flooring after curing (Without Water) 2. Electrical Supply on the site single phase/three phase points at different places. 3. Provide electrical cables near to the installation machinery.

Limit of Supply

1.Provide place to store the material to be installed. 2. Be responsible for the safe custody of all material. 3. Provide place to safely store all the tools of installation. 4. Provide change & rest room for the workers.

The supply included only those mentioned in the quote & does not include below:

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault
Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

General conditions of Aircraft Hangar Door

1. Continuous uninterrupted access to any single door section or as agreed separately.
2. A clear floor area of 4 meters each side of the door leaf must be available during the curtain fitting process. The floor should be finished or if this is not possible, adequate temporary protection be made available to prevent damage to the curtain material.
3. 400 volt / 50Hz 3 phase isolator to be fitted to within 1 meter of the door main control panel. If not available at the start of installation, a temporary supply is acceptable. Any return visits to commission the doors due to permanent power not being available will be charged as appropriate.
4. Provision of 230 Volt power supply (by others) for hand tools.
5. A dry and secure area, not in direct sunlight, is to be provided for storage of the door components.
6. Access to site between 7 am to 11pm six days per week. If this is not possible the installation programme may require amending.
7. Any storage costs for materials due to delays outside of Mega door's control will be charged to the main contractor.
8. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practices. We reserve the right to extend the period accordingly.
9. Any passes required for the project, are the responsibility of the Customer and Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 25 days / door subject to complete clearnce from client, approval on drg, work method statement signed and stamp, receipt of confirmed purchase order, Advance Payment.
Payment	: 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Vijay Tarak** on 8551093333

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd