NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Aditya Constructions
Plot NO. 128, Flat No. 3, Usha Apt. ,Nr. Sadhu Vaswani Garden
Pimpri, 411017
Pune, Maharashtra

Date : 13.02.2021
Quote NO : SQT.20.21.3017
Kind Attn : Mr.Ashok
Email Id : adityaconstructionpune@gmail.com
Contact No: 9011042905

Project Name & Location: Navi Mumbai

Subject : Quotation for Steel Door and 2 Hrs Fire rated Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2,3
C.	General Conditions	4
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Single Leaf Steel Door	1200	2400	1	46,000	46,000	15,000	15,000
2	Single Leaf Steel Door _Including Panic Bar & Accessories	1200	2400	1	64,000	64,000	15,000	15,000
3	2 Hrs Fire rated Door	1200	2400	1	69,000	69,000	15,000	15,000
				Total		**179,000**		**45,000**
				P&F Charges	3%	**5,370**		
				Total Without Taxes		**184,370**		**45,000**
				GST Extra @ 18%	18%	33,187		8,100
				Total With Taxes		**217,557**		**53,100**
				Transportation Charges		**Extra at Actual**		
				Unloading Charges @ Site		**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Single Leaf Steel Door without Panic Bar

Sr. No	Description	Steel Door
1	Description	General Purpose Steel (HMPS) Doors Single Leaf Hinge Type 0.80mm thick M.S. Sheet cladded 40mm thick shutter infill material as Honeycomb complete with M.S. frame (Single Rebate – 100 x 57mm) made from 1.20mm thick M.S. Sheet & Fixing arrangements. Finish – Paint Finish.
2	Door Size	1200mm (W) x 2400mm (H)
3	Accessories	S.S. Ball Bearing Hinges - 04 nos
		S.S. 'D' Type Handle - 01 Nos
		Dead Lock with Cylinder - 01 Nos
		Vision Panel with Non - Fire Rated Glass of Size: 200 x 300mm (6mm Thick Clear
		Heavy Duty Door Closer – Dorma Make TS 68
		Door Stopper - 01 Nos

Single Leaf Steel Door With Panic Bar & Accessories

Sr. No	Description	Steel Door
1	Description	General Purpose Steel (HMPS) Doors Single Leaf Hinge Type 0.80mm thick M.S. Sheet cladded 40mm thick shutter infill material as Honeycomb complete with M.S. frame (Single Rebate – 100 x 57mm) made from 1.20mm thick M.S. Sheet & Fixing arrangements. Finish – Paint Finish.
2	Door Size	1200mm (W) x 2400mm (H)
3	Accessories	S.S. Ball Bearing Hinges - 04 nos
		Panic Bar Exit Device for Single Leaf Door - 01 Nos
		External Trim bar Panic Latch - 01 Nos
		Vision Panel with Non - Fire Rated Glass of Size: 200 x 300mm (6mm Thick Clear Toughened Glass) - 01 Nos
		Heavy Duty Door Closer – Dorma Make TS 68
		Door Stopper - 01 Nos

2 Hrs Fire rated Door

Sr. No	Description	2 Hrs Fire rated Door
1	Description	Fire Resistant Door Single Leaf Hinge Type (2 Hour Fire Rated) 1.20 mm thick G.I Sheet cladded 46mm thick shutter with infill Material Mineral Wool (Density – 96 Kg/M3) complete with G.I. frame (Single Ribet – Frame Profile 100 x 57mm) made from 1.60mm thick G.I. Sheet & Fixing arrangements AS PER BS 476 (PART- 20 &22); IS: 3614 (Part-II) for Integrity, Stability. Paint Finish.
2	Door Size	1200mm (W) x 2400mm (H)
3	Accessories	S.S. Ball Bearing Hinges - 04 nos
		Panic Bar Exit Device for Single Leaf Door - 01 Nos
		External Trim bar Panic Latch - 01 Nos
		Vision Panel with Fire Rated Glass of Size: 200 x 300mm (6mm Thick Clear Toughened Glass)
		Heavy Duty Door Closer – Dorma Make TS 68
		Concealed Flush Tower Bolt - 01 Nos
		Door Stopper - 02 Nos

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 3-4 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% along with confirmed purchase order & Balance before dispatch

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd