NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Topband India Pvt Ltd
Plot A-22/10, Chakan Industrial Area
Phase II, Khalumbre, Pune,410501

Date : 09.03.2021
Quote NO : SQT20-21.2964 R3
Kind Attn : Mr.Prasad Chavan
Email Id : prasad.chavan@topband.in
Contact No: 9767100791

Subject : Revised Quotation for NIHVA make Hydraulic Dock Leveller and Pit Mounted Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Make Dock Leveller 15 Ton**	2000	2500	1	210,000	210,000	**Inclusive**	
2	**Pit Mounted Scissor Lift - 3 Ton**	2000	2000	1	330,000	330,000	**Inclusive**	
				Sub Total		**540,000**		
				Discount 5%		**27,000**		
				Grand Total		**513,000**		
	P&F Charges					**NIL**		
	Total Without Taxes					**513,000**		**-**
	GST Extra @ 18%			18%		**92,340**		-
	Total With Taxes					**605,340**		**-**
	Total Supply + Installation With Taxes							**605,340**
3	Transportation Charges					**Inclusive**		
4	Unloading Charges @ Site					**Inclusive**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Make Dock Leveller





Sr. No.	Description	Specifications
1	Capacity	10 Ton/ 15 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 / (-) 150 mm
7	Platform Size (W x L)	2000 mm x 2500 mm
8	Lip size (W x L)	2000 x 400 mm
9	Shut Height	480 mm
10	Maximum slope can be achieved	10%
11	Clear Pit dimensions (W x L x D)	(W) 2050mm x (L)2500 mm x (D)480 mm
12	Hydraulic power pack	Standard
13	Driver type	Direct by electric Motor
14	Motor Ratings	1 H.P
15	Pump design flow	2.5 LPM
16	Pump pressure	120 bar Operating 200 bar Max.
17	Safety valve set pressure	120 Kg/cm²
18	Pump Type	Gear
19	Volume of oil receiver	7 Lit
20	No Of Deck cylinder	2 No
21	Lip Cylinder	1 No
22	Pair of Dock Bumper	Included

Pit Mounted Scissor Lift



Sr. No.	Description	Specifications
1	Capacity	2 Ton / 3 Ton
2	Platform size	(W) 2000 mm X (L) 2000 mm
3	Shut ht	400 mm
4	Max ht	1700 mm
5	Lift ht	1300 mm
6	Power pack	3PH 3Phase
7	Safety Railing	on 2 side (900 mm height)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom,
Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	**Client Scope**
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	**Nihva Scope**
3	Electrical Supply on the site single phase/three phase points at different places.	**Client Scope**
4	Any civil / masonry/structural work required	**Client Scope**
5	All structure support required	**Client Scope**
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	**Client Scope**
7	Conduits, Cables required	**Client Scope**

D) Terms & Conditions

Price : For Site delivery

Delivery : 4 to 5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 30% Advance along with P.O. , 60% After Delivery of material on site remaining 10% immediate after installation.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr Ravindra Kharat on 7410169333**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd