NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/18-19/1609 **Date : 08-05-2019**

Ferrero India Pvt Ltd
IMSOFER Division (Unit I) ,Plot No. F-13,
M.I.D.C., Baramati, Pune - 413133
Maharashtra, India

Kind Attn: Mr. Bhushan Danawade
Email: bhushan.dhanawade@ferrero.com
Contact No: 9011020268

Subject : Quotation for Assa Abloy_Crawford_Telescopic Dock Leveller

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Assa Abloy_Crawford_Telescopic Dock Leveller (100% Imported with all components – made in Europe)**				
1	**Size : (W)2000mm x (L)3000mm Model : DL6020TI**	1	No	6,59,000	6,59,000
	Specification :				
	1. Standard Frame				
	2. Tear plate thickness 8mm				
	3. Capacity 6 Ton				
	4. lip extension 1000mm				
	5. steel lip bevelled 40mm				
	6. paintclass 80µm				
	7. RAL 5010				
	8. control unit 950 Docking LA TD				
	9. Nominal voltage: 400V 3-phase				
	10. EPDM Seal (Platform /frame)				
	Total				**6,59,000**

GST Pune	27AAECN0437H1ZM

Amount in words	Rupees Six Lack Fifty Nine Thousand Only

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	14-16 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**GST**	:	Extra @ 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 08551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For Nihva Technologies Pvt Ltd