NIHVA TECHNOLOGIES PVT. LTD.

# Sales Quotation

**Quotation No - SQT/17-18/0030R** **Date : 18-08-2017**

**Emcure Pharmaceuticals Ltd**
Survey No. 255/2
Phase-I, Rajiv Gandhi IT Park
MIDC, Hinjewadi, Pune, Maharashtra 411057

**Kind Attn : Mr.Sarjerao Shinde**
**Email :** Sarjerao.Shinde@emcure.co.in
**Contact No :** 9370511231

**Subject : Quotation for Conveyor**

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

**Commercial Offer**

| Sr.No | Description | Qty | Unit | Rate In INR | Net Amount INR |
|---|---|---|---|---|---|
| 1 | **Conveyor Make - NIHVA (HSN CODE : 8428.00.00)** | | | | |
| Technical Specifications | 1.Conveyor Width : 500 -550mm | 1 | No. | 4,00,000 | 4,00,000 |
| | 2.Material To Be Handle : Boxes/ Bags | | | | |
| | 3.Weight Of The Box/Bags: 150 kgs | | | | |
| | 4.Size of Box/Bags:600 (L) x 250 (W) x 300 (H) (OVERALL) | | | | |
| | 5.Temperature: Ambient | | | | |
| | 6.Length of conveyor: 13200mm | | | | |
| | 7.Height of Conveyor: 5700mm | | | | |
| | 8.Tilting Angle: 20-22 degree | | | | |
| | 9.Port Extension Length: 1.5 mtr at both sides | | | | |
| | 10.Belt type: PVC Belt | | | | |
| | 11.Main Body Of Conveyor: Manufacturing from MS Plate, Tube Frame Structure | | | | |
| | 12.Panel:The conveyor comes with a fixed main panel on rear side and front side only operating panel with emergency stopper sensor bar , LED lighting , totally consoled wiring. | | | | |
| | 13.Installation Charges for above Conveyor | | | 10,000 | 10,000 |

| | |
|---|---|
| **GST PUNE:** | 27AAECN0437H1ZM |
| **GST GUJRAT:** | 24AAECN0437H1ZS |

| | | |
|---|---|---|
| **Amount in Words** | **Total Amount in INR** | **4,10,000.00** |
| | **Rupees Four Lacs Ten Thousand Only** | |

**General Prerequisites Required at Site**

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

**Limit of Supply**

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

**Quote/Supply is based on**

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

**The supply included only those mentioned in the quote & does not include**

1. Unloading from truck placement on site
2. Electrical connection for control panel.

**Client Scope**

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
6. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

**Terms and Conditions :**

| | | | |
|---|---|---|---|
| 1 | **Price** | : | Ex. Works Pune |
| 2 | **P & F Charges** | : | 3% Extra on total supply value |
| 3 | **Freight Notes** | : | Extra as applicable |
| 4 | **Delivery** | : | 9-10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval. |
| 5 | **Payment** | : | 100% advance along with confirm Purchase Order. |
| 6 | **Insurance** | : | Extra if applicable |
| 7 | **Tax** | : | GST: 28% applicable on total supply value |
| 8 | **Validity** | : | Validity of Offer is 15 days from the of quotation |
| 9 | **Warranty** | : | 12 Months from the date of supply |

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards
Pooja Badre
7709586333
For Nihva Technologies Pvt Ltd