NIHVA

NIHVA Technologies Pvt. Ltd.

Retractable Roof Proposal



Dear Mr. K Ponnarasu

"NIHVA Technologies Pvt Ltd" are the prominent manufacturer, importer, exporter of a comprehensive assortment in Automation solution and Door Automation establish in 2012. We has in introduced many innovation in Smart Roofing or Retractable Roof.

A **Retractable roof** is a roof system designed to roll back the roof on tracks so that the interior of the facility is open to the outdoors.

Retractable roof is the new kind of innovation done for Bungalows, Hotels, Hospitals, Villas, Apartments, Commercial, where we can add more glory by allowing partial sunlight to enter in premises at day and sky view at night.

Proposal and Quote

Sales Person: - Pradip Yejare

Client Name: - Mr. K Ponnarasu

Project Name: - Retractable Roof

Project Location: - 1st A Cross Road, Kaggadasapura Main Road, C V Raman Nagar, Bengaluru, Karnataka 560093

Date: - 19-12-2019

Quotation No: - SQT19.20-2307

NIHVA Technologies Pvt Ltd.

187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad. Pune – 411019

TÜV INDIA

TÜV NORD GROUP

Quotation

Technical Specification:-

- Polycarbonate Israel make Compact/Embossed 4.0 mm thick
- Profile- Powder Coated AL Frame (As per RAL Colour)
- Guide- Anodized AL Guide
- Control Panel
- Motors with Remote Control
    a) Italian Make BFT Brand
    b) Single Phase Bi-directional Motor
    c) Speed- 09-12m/min
    d) Rack and Pinion Arrangement -Z16/Molude4/Module6
    e) Mechanical Limit Switch
- **Size** – 16m (w) x 25m(L) x 3m (H)- 8 segment

Commercial Specification:-

Supply + Installation Price	60,00,000 INR
P&F Charges	1,80,000 INR
GST 18%	11,12,400 INR
Total with Taxes	72,92,400 INR

*Transportation as per actuals and Unloading in Client scope

NIHVA Technologies Pvt Ltd.

187, G-Block, 1st Floor, Above Renault
Showroom, Thermax chowk, MIDC,
Chinchwad. Pune – 411019

NIHVA Technologies Pvt. Ltd.

Warranty

- 10 years for Polycarbonate Sheet.
- 5 years for Powder Coated Aluminium Profile.
- 1 year for motor.
- 1 Year from the date of supply.

General condition-

- Installation will start after receiving of site Readiness Photographs or written Email Communication
- We will mobilize the installation Team in 3-4 Working days, after receipt of site Readiness Confirmation
- For any reason if we need to stop our installation and demobilize Team without Completing the work, then extra cost will be applicable for remobilizing the team.

These items are not included in the offer

- Secured and fully Covered Store area to keep the material
- Scaffolding/Hydra/Carne/Forklift etc. - Required for installation at site
- Electrical Supply on the Single Phase/ three phase point at different places
- Any civil/masonry/ structural work required
- In case of any changes in layout as per site requirements after the shipment of material, the additional quantities and the wastage

Terms and Conditions

- Price - EX Works Pune
- Delivery – 3 - 4 months from date of receipt of Confirmed Purchase order, Advance Payment and Drawing approval.
- Payment – 80% Advance along with Confirmed Purchase order and Balance before dispatch.
- Validity – Validity of offer is 15 days from the date of quotation.

NIHVA Technologies Pvt Ltd.

187, G-Block, 1st Floor, Above Renault
Showroom, Thermax chowk, MIDC,
Chinchwad. Pune – 411019

TÜV INDIA
TÜV NORD GROUP