NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

shimzu Carporation
No.2 Prestige Emerald, 5th Floor Lavelle road,
Madras Bank, Bangalore - 560001
Karnataka -India.

Date : 23.08.2019
Quote NO : SQT/19-20/1776R2
Kind Attn : Mr. Pawan
Email Id : pawankumar.singh@shimz.biz
Contact No: 9108965202

Subject : Quotation for Motorized Sliding Gate, Wicket Gate and Dock Shelter. (Project - Honda Motor cycle & scooter india pvt ltd)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	MOTORISED SINGLE LEAF SLIDING GATE	8000	1200	2	345,000	690,000	20,000	40,000
2	MOTORISED SINGLE LEAF SLIDING GATE	9000	1200	1	374,000	374,000	20,000	20,000
3	AUTOMATIC 2 LEAF TELESCOPIC SLIDING GATE	13300	1200	1	773,000	773,000	25,000	25,000
4	AUTOMATIC 3 LEAF TELESCOPIC SLIDING GATE	20000	1200	1	1,170,000	1,170,000	25,000	25,000
5	WICKET GATE	1200	1200	4	35,000	140,000	10,000	40,000
6	BOOM BARRIER - 4M Length			2	115,000	230,000	10,000	20,000
7	BOOM BARRIER - 5M Length			2	140,000	280,000	10,000	20,000
8	BOOM BARRIER - 6M Length			3	140,000	420,000	10,000	30,000
9	Dock Shelter	3600	4000	7	130,000	910,000	15,000	105,000
				Total		**4,987,000**		**325,000**
6	P&F Charges			3%		149,610		
	Total Without Taxes					5,136,610		325,000
	GST Extra @ 18%			18%		924,589.80		58,500
	Total With Taxes					**6,061,200**		**383,500**
7	Transportation Charges					In Client Scope		
8	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA make – Motorized Sliding Gate	
Door type	**Motorized Sliding Gate**
Opening Direction	**Horizontal - from left to right or reverse**
Mounting Location area	Inside area
Design Pattern	Standard Tubular Design Pattern
OUTER TUBE	72 x 72 x 3.2mm MS SQ. TUBE
FOR POST	72 x 72 x 3.2mm MS SQ. TUBE
INNEAR TUBE	38x38x3.20mm/40x40x3.2 MS SQ. TUBE
Gap Between Tubes	125mm
Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
Guide Rollers supporter during Gate movement	**Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate**
Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
El motor make	BFT – Italy (100% imported)
Emergency Operation	Manual after turn the switch
Operating Switch	Push Button from inside
Safety	Photocells, Flashing Light

BOOM BARRIER
Each Boom Barrier Set include: **MICHELANGELO BT A Barrier-1No.** **• Round Boom First part-1No.** **• Round Boom Second part- 1 No.** **• Anchor Base- 1No.** **• MOB. Boom Rest-1No.** **• Rubber Safety Profile- 1No.** **• OMEGA AT Acce. - 1No.** **• Transmitter with Channels- 1No.** **• Push Button**
Dock Shelter
Clear Opening dimension : (W) 3600 mm x (L) 4000 mm **• Curtain colour : Black** **• Parking Guides : White, Yellow** **• Wall Fixings : Concrete, Sandwich light Concrete, Load house cavity, insulated panel** **• Top & Side Curtaiins : Double Layer High Quality Polyester** **• Thickness : 3.0 mm** **• Weight : Approx 3400 g/m2** **• Thickness : 0.5 mm**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6-7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd