NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1691R **Date:- 19.06.2019**

Trident Group
E-212 Kitchlu Nagar, Ludhiana

Kind Attn: Mr. Sachin
Email ID: SachinSingla@tridentindia.com
Contact No: 8349801399

Project Name And Location :

Subject : Quotation for High Speed Door RR300S

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Albany Make Rapid Roll Up Door RR300S** **(100% Imported with all components – made in Germany)** **(Supply + Installation)**				
Construction:	High-Speed Roller Door with transparent curtain and reinforcement stripes according to the following RAL colours: blue (RAL 5002) or red (RAL 3002)				
Side frames:	Side frames galvanized, bottom rail profile made of aluminium				
Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)				
Control system :	Controls ACS 50, IP 55 for opening / closing speed approx. 1,0 m/s. Control box with Up-Stop-Down button. For dimensions > 3500x3500mm it is obligatory to use a frequency converter control ('MCS-FC or MCC)				
Power supply:	3/(N)/PE/230/400/415 V, 50 Hz.				
Safety features:	Safety edge, safety photocell Transmitter / Receiver inside side frames, emergency crank and mechanical drop-down protection.				
1	Size : (W) 1800 mm X (H) 2700 mm	4	No	4,15,000	16,60,000
	Total				**16,60,000.00**

GST Pune	**27AAECN0437H1ZM**	

TOTAL BASIC AMOUNT	**16,60,000.00**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	NIL
3	**Freight Notes**	:	Extra As applicable
4	**Delivery**	:	8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment and Drawing approval
5	**Payment**	:	80% advance along with confirm purchase order and balance before dispatch
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST @18% Extra
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply

Please feel free to contact **Mr. Arjun Patil** on **8551096333** for any further Clarification /Information in this Concern.

With Best Regards

Varsha

8551091333

For NIHVA Technologies Pvt Ltd