NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax
chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Godrej Consoveyo Logistics Automation Ltd.
701, A Wing, Reliable Tech Park
Off Thane - Belapur Road, Airoli, Navi Mumbai – 400708. India

Date : 12.11.2020
Quote NO : SQT.19.20.2550R
Kind Attn : Mr Dileep Jadhav
Email Id : dileep.jadhav@godrejconsoveyo.com
Contact No: 9920543702

Subject : Revised Quotation for Telescopic Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Page
A.	Commercial Offer	**1**
B.	Technical Specification	**2**
C.	General Conditions	**3**
D.	Terms & Condtions	**3**

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Total length of conveyor (mm)	Width Of Conveyor (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Telescopic Conveyor with 1 year Warranty	12500	1300	1	1,175,000	1,175,000	Inclusive	-
2	Extended 1 year Warranty for 8 hrs per working day			1	75,000	75,000	Inclusive	-
3	Extended 1 year Warranty for 16 hrs per working day			1	125,000	125,000	Inclusive	-
				Total		**1,375,000**		**-**
4	P&F Charges			3%		**41,250**		
	Total Without Taxes					**1,416,250**		**-**
	GST Extra @ 18%			18%		254,925		-
	Total With Taxes					**1,671,175**		**-**
5	Transportation Charges					**Included**		
6	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Description	Specification
Total length of conveyor	12500 mm
Collapsed length	4500 mm
Telescopic Length	8000 mm
Width Of Conveyor	1350 mm
Width Of Conveyor Belt	600 mm
Conveyor Capacity	15 kg/mtr
Speed	30 mtr/min (Variable Speed)
Drive Type :	
Conveying	Auto/Manual
Telescopic	Auto/Manual
Hydraillic Lifting Support	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax
chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Shailesh Bhoir
7291206333
For NIHVA Technologies Pvt Ltd