WORK ORDER

Client				
Tenneco Clean Air India Private Limited	PO Number:	4502214460	W. O. no-	SO/20-21/29
Address:	PO Dated :	31-Aug-20	W. O. Date	05-Sep-20
Gat no. - G6 Phase - III,Chakan MIDC Kuruli, Khed taluka, Maharashtra 410501	PO Received Date:	04-Sep-20	Sales Co ordinator	Varsha
	Ref. Quotation:	SQT.20.21.0047	Front Sales Person	Arjun

Contact Details		Billing Address:	Dispatch Address:
Contact Person:	Mr. Abhijit Ghodekar Mr. Digambar Parkhi	Gat no. - G6 Phase - III,Chakan MIDC Kuruli, Khed taluka, Maharashtra 410501	Gat no. - G6 Phase - III,Chakan MIDC Kuruli, Khed taluka, Maharashtra 410501
Email ID:	AGhodekar@Tenneco.com		
Mobile:	Mr. Abhijit Ghodekar - 7620223665		

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply	Installation	Amount	Dwg. Approval
1	**Albany make Machine protection door RP 300**	**Size : (W)1800 x (H)2000 mm**	**NO**	**2**		**Included in supply price**	-	**Pending**
			Total	**2**			-	

Sr. No	Description	Specification
1	Door version:	Vertical Rapid Roller Door for machine protection. RP300
2	Side Frames:	Aluminum anodized two parts, to have easy access to switches and service.
3	Door blade:	Rolltex Plus Curtain with RAL Blue 5002
4	Bottom beam	Aluminium anodized.
5	Drive unit:	Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)
6	Opening / closing speed:	Approx. max. 2,4 / 1,7 m/s
7	Control system:	MCC Vector Control
7	MCC Type	Standard version
7	MCC Display type	Display delivered separately, not mounted
8	Power suppy:	3/(N)/PE 230/380/400/415 V, 50 Hz
9	Safety features:	Pre running photocell at the bottom profile
9	Photocell	with photocell
10	Safety limit switch:	1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.
11	Window Type	700 x 500 mm Anti UV Type
12	Window Qty	1 No

A) Commerical Terms

1)	**Payment Terms:**	50% Advanc ae, 40% after GRN and 10% after installation
2)	**Delivery Date as per PO:**	8 to 9 weeks from date of drawing approval
3)	**Transportation:**	Client
4)	**P&F Charges:**	nil
5)	**Loading:**	NIHVA
6)	**Unloading:**	Client
7)	**Lifting Equipments:**	Client
8)	**Warranty:**	12 Months from date of Supply
9)	**Height arrangement:**	Client
10)	**Electricity Supply:**	Client
11)	**GST:**	18% Extra
12)	**Installation Scope:**	NIHVA
13)	**Mode of import:**	by Sea
14)	**HSS:**	High Sea Sale
15)	**Documentation Required:**	High Sea Sale documents

Certified that the above work order finalised in presence of:

AGM	SALES	PROJECT	PPC	DESIGN	Date & Time
A.K.	**A. P.**	**S. P.**	**S.B.**	**P. A.**	