×

Technical Bid

Vendor : NIHVA Technologies Pvt. Ltd.

1. CEILING WORKS RETRACTABLE ROOF FOR ADRL EXPERIMENTAL BAY

Sl.No.	Specification	Value	Compliance	Offered Specification	Remark
1	Roofing Area	9.1m x 6.7m (including 0.6m overhang at three sides)	YES	(w) 5.5 m X (L) 8.7 m - 5 Panels	As per Site visit & discussion with ADRL unit
2	Type of Retractable roof	Sliding/Telescopic Type with minimum 5 segments to cover the entire bay (including fixed segment).	YES		
3	Material of Construction	• Roofing Sheet/Panels: Non-corrosive Aluminium Alloy Panels (Powder Coated/Anodic Oxide Coated) with minimum thickness of the roofing panel of 1 mm. • Track Mounting Base frame structure above the walls to suitably hold the retractable roof: Stainless Steel 304 grade •Tracks/Guides: Non-corrosive Aluminium Alloy (Powder Coated/Anodic Oxide Coated) extruded tracks • Profiles/Frames: Non-corrosive Aluminium Alloy (Powder Coated/Anodic Oxide Coated) hollow extruded profiles • Sealing of Enclosures: Sealing between Aluminum panels and structural members shall be provided (100% leak proof and 100% water resistant). •Any additional steel structures, brackets and fasteners for the assemblies to hold the retractable roof: Stainless Steel 304 grade	YES		
4	Mode of Operation	Provisions for Remote Operation as well as manual mode of operations shall be provided. Remote operation shall be from the adjacent building with approximate distance of 25 metres through wired connection. Manual operation provision shall be provided near the installation site.	YES		
5	Features of Drive Motor	• Rack and pinion arrangement • Power Supply: 230V AC, 50Hz • Mechanical Limit Switch • SS304 Mounting Base • Built in Control Board	YES		
6	Environmental Protection of Drive Motor	Motor shall be provided with proper sealing to have rain, humidity and dust protection. Motor shall be suitable for outdoor operations (IP 56 level or above shall be provided).	YES		
7	Electrical Fittings	• End Limit Switches to indicate status LED on the control room 25 meters away from the site.	YES		

		• Control switches shall be provided near the site as well as inside the control room adjacent to site at a distance of 25 meters.			
8	Safety Interlocks	Safety interlocks for the electrical motor shall be provided with interlock switches.	YES		
9	General Terms	• All the Aluminium structures shall be made with Non-corrosive Aluminium Alloy (Powder Coated/Anodic Oxide Coated). • All the steel structures shall be made with Stainless Steel 304 grade material.	YES		
10	Demonstration & Training	Demonstration of operation as well as training to the operators shall be provided at site.	YES		

General Specifications

Sl.No.	Specification	Value	Compliance	Offered Specification	Remark
1	Warranty	Overall warranty of all the systems of the retractable roof should be minimum 2 years. Warranty for individual components should be same as the warranty offered by the manufacturer for individual components.	YES		
2	Annual Maintenance Contract	Party must quote for a Comprehensive Annual Maintenance Contract (AMC) for a period of FIVE years after the warranty period is over. A separate order for AMC with detailed terms and conditions will be issued after the completion of the warranty period. Party must visit based on Preventive Maintenance procedure and schedule and attend any number of break down calls.	YES		
3	Training	Demonstration of operation as well as training to the operators shall be provided at site.	YES		
4	General requirements	Transportation, unloading, scaffolding, installation charges including any additional stainless steel structures, electrical line routing from control room (25 meters away) and any other charges related to commissioning of the retractable roof shall be under the purview of the supplier.	YES		
5	Installation & Commissioning	Installation and commissioning shall be done by the party at the site. All the necessary arrangements towards installation and commissioning of the system shall be arranged by the vendor.	YES		