NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

British American Tobacco
Dhaka Bangladesh

Date : 16.04.2022
Quote NO : **MHE_22.23.0002**
Kind Attn : Mr. Asif Khan
Email Id : asif_khan@bat.com
Contact No: 88 01736373736

Project Name & Location: British American Tobacco, Dhaka Bangladesh

Subject : Quotation for Telescopic Belt Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Belt Conveyor with Inclined Conveyor as Feeding conveyor** • Total Length- 12mtr (Fixed-5mtr, Extended-7mtr) • Inclined Conveyor - 1.5mtr length • Capacity- 15-20 boxes/min • Belt Width - 600 mm	1	20,50,000	20,50,000	1,25,000	1,25,000
	TOTAL EXCLUDING TAXES			20,50,000		1,25,000
2	Local Taxes & Duties		**Extra At Actual**			
3	P&F Charges		**Extra At Actual**			
4	Transportation Charges		**Extra At Actual (On FCA Basis)**			
5	Insurance Charges		**Extra At Actual**			
6	Unloading Charges @ Site		**In Client Scope**			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Conveyor

Sr. No.	Parameters	Specification
1	Material to be conveyed	Boxes
2	Size of boxes	480mm x 380mm x 450mm
3	Weight of box	16 Kg
4	Capacity	15-20 boxes/min
5	Belt Width	600 mm
6	Belt Type	2 Ply 3.2 mm PVC
7	Conveyor Type	Collapsible boom type hinged Telescopic belt conveyor
8	Length Of Conveyor	Fixed Length : 5000 mm Telescopic (Expanded) : 7000 mm Total Length : 12000 mm
9	Main Body Of Conveyor	MS Powder coated
10	Direction	Both Forward and Reverse direction
11	Conveyor Height	Min.700 - 800 mm
12	Inclination Height	1200 - 1400 mm
13	Gear Box	Bonfiglioli
14	Driven Motor Make	SEW , IE2
15	Movement	Wheel for easy movability

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will depute 2 site engineers who will assist your team for doing installtion for 6-7days.

3 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

4 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

5 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-10 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 60% Advance along with Confirmed Purchase Order.
35% Along with Approval of Drawing and before start a Production.
5% Against completion of Installation, Testing and Commissioning

Validity : Validity of Offer is 15days from the date of quotation.

Warranty : 12 months from the date of supply.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd