NIHVA TECHNOLOGIES										
Weight Estimation Sheet										
CLIENT	**Unipack-Supa**							**DATE**	**06-01-2024**	
PROJECT	**Sliding Gate**							**LOCATION-**	**Pune**	
FINISH SIZE	**9.7M*1.8M**									
	Sizes (In mm)									
Description	**Material Grade**	**Sp.Gravity**	**Dia**	**Width**	**Height**	**Thickness**	**Length**	**QUANTITY**	**WEIGHT (KG)**	**AS DWG.**
A.Tube-Outer Frame	**MS**	**7.85**		**100**	**50**	**2**	**9700**	**2**	**88.9**	27.35
B.Tube- Vertical Support	**MS**	**7.85**		**100**	**50**	**2**	**1700**	**7**	**54.6**	17.77
C.Tube- Vertical Support	**MS**	**7.85**		**50**	**50**	**1.5**	**1700**	**42**	**163.1**	211
D. Sheet	**MS**	**7.85**			**550**	**1**	**9500**	**1**	**31.0**	0
Post ISMC 100	**MS**	**7.85**					**2450**	**10**	**245.0**	239
MS BAR (in metre)	**MS**	**7.85**	**16**				**14**	**1**	**22.1**	22.12
IF ISMC 125 IN OUR SCOPE THEN(in metre)	**MS**	**7.85**					**14**	**1**	**177.8**	183.4
							Weight For Single Quantity		**782.5**	700.64
							Weight For Required Quantity	1	782.5	
							Weight Including Safety Factor	1.2	939.0	

Prepared by
Jayesh Shinde

Weight criteria.	NIHVA	FROM PROVIDED DWG
GATE LEAF	337.6	256.12
STRUCTURE MTG	444.9	444.52
TOTAL	782.5	700.64