Client : M/s. Amar Tea Umargam.
Job: Filling THROUGH PUTS. **Revised on Date: 21.12.17.**

Area of Room (Size)	Sr.No.	MACHINE	SPEED IN PACKS	SPEED IN Kg	CAPACITY (1 HOUR)	CAPACITY (7 HOUR)	TIME OF BIG BAG 350Kg ON MACHINE	THROUGH PUT	REMARKS	
		(a)	(b)	(c)	(d)	(e)	(f)	(g)		
				(a x b)	(c x 60)	(d x 7)	(350 / c)	(60 / f)		
		(kgs)	(pouch/min.)	(kg/min.)	(kgs)	(kgs)	(min.)	(bags/hour)		
7x5 = 35 m2	1	5	20	100	6000	42000	7.00	8.57	For 2no big bags each of 350 kg	Gussetted Pouch
7x5 = 35 m2	2	1	50	50	3000	21000	7.00	8.57		Penta seal Pouch
7x5 = 35 m2	3	0.5	65	32.5	1950	13650	5.38	11.15	1 no 350kg big bag supplying to 2 machine	CASE LINER Box
7x5 = 35 m2	4	0.5	65	32.5	1950	13650				CASE LINER Box
7x5 = 35 m2	5	0.25	120	30	1800	12600	5.83	10.29		Centre seal Pouch
7x5 = 35 m2	6	0.25	120	30	1800	12600				Centre seal Pouch
7x5 = 35 m2	7	0.25	120	30	1800	12600	5.83	10.29		Centre seal Pouch
7x5 = 35 m2	8	0.25	120	30	1800	12600			Future	Centre seal Pouch
7x5 = 35 m2	9	0.1	150	15	900	6300	23.33	2.57	Twin Line	Centre seal Pouch string
7x10 = 70m2	10	0.05 OR 0.03	600	30	1800	12600	5.83	10.29	Two Machine	Centre seal Pouch string
7x10 = 70m2	11	0.05 OR 0.03	600	30	1800	12600			Two Machine	Centre seal Pouch string
7x10 = 70m2	12	0.025 OR 0.016	600	15	900	6300	11.67	5.14	Two Machine	Centre seal Pouch string
7x10 = 70m2	13	0.025 OR 0.016	600	15	900	6300			Two Machine	Centre seal Pouch string
7x5 = 35 m2	14	Jar 1kg	40	20	2400	8400	17.50	3.43		Jars
3.6x6.7 = 24.12 m2	15	0.025	160	4	240	1680	29.17	2.06	Twin Line	Centre seal Pouch string
	16	0.05	160	8	480	3360			Twin Line	Centre seal Pouch string
NEW	17	0.5	120	60	3600	25200	5.83	10.29	NEW	Penta seal Pouch
NEW	18	0.25	240	60	3600	25200	5.83	10.29	NEW	Centre seal Pouch
							Total =	**92.94**		