NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Hettich India Pvt. Ltd.
302, Durolite House | Opp SAB TV, New Link Road
Mumbai-400053

Date : 20.01.2021
Quote NO : **SQT.20-21.2439 R1**
Kind Attn : Mr.Nitin Juneja
Email Id : nitin.juneja@hettich.com
Contact No: 9205877118

Project Name & Location:Primary Packaging machine with Bowl feeder,Mumbai

Subject : Quotation for Primary Packaging machine with Bowl feeder, Indexing Conveyor etc.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Primary Packaging Machine	1	9,28,793.00	**9,28,793.00**		
2	Bowl feeder 1 (D500)	3	2,16,718.00	**6,50,154.00**		
	Bowl feeder 2 (D 400)	1	1,93,498.00	**1,93,498.00**		
	Gate assmebly	4	61,920.00	**2,47,680.00**		
	Indexing Flat belt conveyor	4	66,564.00	**2,66,256.00**		**1,20,000.00**
	Indexing conveyor	1	5,80,495	**5,80,495.00**		
	Cuopon Vacuum lift mechanism(pick and place unit and vacuum unit)	1	4,74,383	**4,74,383.00**		
	Outfeed Conveyor	1	1,16,099	**1,16,099.00**		
	Automation Charges	1	7,73,994	**7,73,994.00**		
		Total		**42,31,352.00**		**1,20,000**
3	P&F Charges	3%		**1,26,940.56**		
	Total Without Taxes			**43,58,292.56**		**1,20,000**
	GST Extra @ 18%	18%		**7,84,492.66**		**21,600.00**
	Total With Taxes			**51,42,785.22**		**1,41,600.00**
4	Transportation Charges			**Extra at Actual**		
5	Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Primary Packaging machine

Parameters	Specification
Product to pack	Metalic hinges
Product size	180x 140/180x 215
Product weight	Please specify
Product line speed	23-25 pouches / min
Contact parts	MS powder coated
Non contact parts	MS powder coated
Gear motor	Bonfiglioli
Servo motor	Mitsubishi
Sensor	Omron/P&F
Foot	Swift
Belt make	Chiorino/Forbo/NTB
Chain make	Dimond
Switch gears	Schiender
HMI	Mitsubishi
PLC	Mitsubishi
Panel	Mitsubishi
Rest	As per Layout
Pneumatics	Festo
Pneumatics	Festo
Electric Actuator	Festo
Vaccum	Schmalz

C) General Conditions

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd