**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**SERUM INSTITUTE OF INDIA PVT LTD**
POONAWALLA BIOTECHNOLOGY PARK
Manjari BK, Tal. Haveli,
Pune 412 307.INDIA .

**Date :** 29.06.2021
**Quote NO :** SQT.20.21.2625R1
**Kind Attn :** Mr. Vijay Kashid
**Email Id :** vijay.kashid@seruminstitute.com
**Contact No:** 7218026128

**Project Name & Location: SERUM INSTITUTE OF INDIA PVT. LTD. Manjari.**

**Subject : Revised Quotation for Pit Mounted Scissor Lift .**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Size | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|
| | | Working Platform (in mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Pit Mounted Scissor Lift** | 2200mm (L) x 1500 mm (W) | 2 | 340,000 | 680,000 | Inclusive | |
| | | | **Total** | | **680,000** | | - |
| 2 | P&F Charges on Total Supply Value | | 3% | | **20,400** | | |
| | **Total Without Taxes** | | | | **700,400** | | - |
| | GST Extra @ 18% | | 18% | | 126,072 | | - |
| | **Total With Taxes** | | | | **826,472** | | - |
| 3 | Transportation Charges | | | | **In Client Scope** | | |
| 4 | Unloading Charges @ Site | | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification -**

**Pit Mounted Scissor Lift**

| Sr. No | Description | Specifications |
|---|---|---|
| 1 | **Capacity** | 3 ton |
| 2 | **Platform size** | 2200mm (L) x 1500 mm (W) |
| 3 | **Shut ht** | 600 mm |
| 4 | **Max ht** | 2100 mm |
| 5 | **Lift ht** | 1500 mm |
| 6 | **Power pack** | 5 HP, 3 PH AC POWER PACK |
| 7 | **Safety Railing** | On length side only |
| 8 | **Color** | as per req. RAL shade. |
| 9 | **Motor** | Outside |
| 10 | **Powerpack** | Outside |
| 11 | **Panel** | Inside |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description |
|---|---|
| 1 | Secured and fully covered Store area to keep the material |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site |
| 3 | Electrical Supply on the site single phase/three phase points at different places. |
| 4 | Any civil / masonry/structural work required |
| 5 | All structure support required |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. |
| 7 | Conduits, Cables required |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333.**

**With Best Regards**
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd