QTN No:- SQT/18-19/0792R4_Channels

Dated : 13.11.2019

Kind Attn:- Ms. Shruti Joshi

Contact No:- 9921395900

Client Name:- Bosch Chassis Systems India Pvt. Ltd.
Gat no. 306, Village Nanekarwadi, Chakan, Pune,

Email Id:- shruti.joshi@in.bosch.com;

Dear Sir,

This is with reference to your requirement of Access Cover , we are pleased to quote competitive rates for **NIHVA Technologies Pvt. Ltd** authorized associated partner of **ACO Systems & Solutions (Germany).** We hope you find our quotation in line with your requirement. Looking forward for offering better solutions in drainage system.

Project: Bosch Limited Chakan

Article No	Product	Total Qty in Nos	Supply Price (Rs.) / Each	Total Supply Amount (Rs.)
	Gr Floor Kitchen Areas With Horizontal Gully - With Sunken Areas			
	(W) 300MM x (L) 630MM Wet Garbage Areas / Dry Garbage Areas / Receiving Areas / Snack Areas / Veg Preparation Areas / Wet Areas / Dish Wash Areas			
416615	ACO hygienic box channel W300/270 L630/600 H60 D142 standard edge, FHD, EN1253, 1.4301	7	30,000	210,000
408079	ACO gully 157 telescopic DN110 horiz.locat.fl. FAT,1.4301,HF	7	14,000	98,000
416864	ACO mesh grating W268 L599,5 E30, mesh 25x25 bar 30x2, antislip, LC L15, 1.4301	7	8,000	56,000
416906	ACO 157MM Gully Silt Basket (Horizontal)	7	3,000	21,000
	(W) 300MM x (L) 630MM Dish Wash Areas CH 01/ CH 2			
Z Number	ACO hygienic box channel W300/270 L630/600 H100 D142 standard edge, FHD, EN1253, 1.4301	2	36,000	72,000
408079	ACO gully 157 telescopic DN110 horiz.locat.fl. FAT,1.4301,HF	2	14,000	28,000
416864	ACO mesh grating W268 L599,5 E30, mesh 25x25 bar 30x2, antislip, LC L15, 1.4301	2	8,000	16,000
416906	ACO 157MM Gully Silt Basket (Horizontal)	2	3,000	6,000
	Channel 02 - (W) 630MM x (L) 930MM (Rice Cooker & Food Preparation Areas) - CH 10 to CH 14			
Z Number	ACO hygienic box channel W600/570 L930/900 H150 D200 standard edge, FHD, EN1253, 1.4301	5	54,000	270,000
408085	ACO hygienic gully 218 telescopic D110 horizontal location flange with FAT, FHD, EN1253, 1.4301	5	18,000	90,000
416876	ACO mesh grating W299 L598 H30 E30, mesh 25x25 bar 30x2, antislip, LC L15, EN1253, 1.4301	15	14,000	210,000
416910	ACO 218 MM Gully Silt Basket (Horizontal)	5	3,000	15,000
	(W) 300MM x (L) 1000MM (Dish Wash Areas) CH 15			
Z number	ACO Hygenic Channel W300/270 L 2530/2500 H 70/50 E20.5 D200 F58 Standard Edge FHD EN 1253 1.4301	1	44,000	44,000
408085	ACO hygienic gully 218 telescopic D110 horizontal location flange with FAT, FHD, EN1253, 1.4301	1	18,000	18,000
416866	ACO Mesh Grating W268 L499,5 H30 E30, mesh 25x25 bar 30x2, antislip, LC L15, EN1253, 1.4301, Cz# 416860	2	11,000	22,000
416910	ACO 218 MM Gully Silt Basket (Horizontal)	1	3,000	3,000

	(W) 300MM x (L) 2530MM (Pot Wash Areas) - CH 17			
Z number	ACO Hygenic Channel W300/270 L 2530/2500 H 100 E20.5 D200 F58 Standard Edge FHD EN 1253 1.4301	1	51,000	51,000
408085	ACO hygienic gully 218 telescopic D110 horizontal location flange with FAT, FHD	1	18,000	18,000
416866	ACO Mesh Grating W268 L499,5 H30 E30, mesh 25x25 bar 30x2, antislip, LC L15, EN1253, 1.4301, Cz# 416860	5	11,000	55,000
416910	ACO 218 MM Gully Silt Basket (Horizontal)	1	3,000	3,000
	W) 330MM x (L) 3530MM (Wet Floor Areas) - CH 18			
Z number	ACO hygienic gully 218 fixed height W300 L300 D110 horizontal with FAT, FHD, EN1253, 1.4301	1	66,000	66,000
408085	ACO silt basket for horizontal gully 218, EN1253, 1.4301	1	18,000	18,000
416866	ACO mesh grating W268 L268 H30 antislip, LC L15, EN1253, 1.4301	7	11,000	77,000
416910	ACO hygienic gully 218 fixed height W300 L300 D110 horizontal with FAT, FHD, EN1253, 1.4301	1	3,000	3,000
	(W) 300MM x (L) 300MM (300MM x 300MM Trap on Floor) - Gully 1 to Gully 5			
408013	ACO hygienic gully 218 fixed height W300 L300 D110 horizontal with FAT, FHD, EN1253, 1.4301	5	26,000	130,000.00
416910	ACO silt basket for horizontal gully 218, EN1253, 1.4301	5	3,000	15,000.00
408034	ACO mesh grating W268 L268 H30 antislip, LC L15, EN1253, 1.4301	5	7,000	35,000.00
	(W) 200MM x (L) 200MM (Floor Gully Corridor)			
97308	ACO gully EG150 tile W150 L150 D75 telescopic, horizontal for mesh grate with FAT, 1.4301	29	11,000	319,000
5964	ACO mesh grate W142 L142 E20, MW 25x25,bar 20x2,electropolished antislip, 1.4301	29	5,000	145,000

	1st Floor Kitchen Areas With Vertical Gully - With Core Cut Areas			
	(W) 300MM x (L) 1530MM (Dish Wash Areas) - CH 19 - CH 20			
Z Number	ACO hygienic box channel W300/270 L1030/1000 H100 D200 standard edge, FHD, EN1253, 1.4301	2	44,000	88,000
408061	ACO gully 218 telescopic DN110 vertical.locat.fl. FAT,1.4301,HF	2	15,000	30,000
416866	ACO Mesh Grating W268 L499,5 H30 E30, mesh 25x25 bar 30x2, antislip, LC L15, EN1253, 1.4301, Cz# 416860	6	11,000	66,000
416910	ACO 218 MM Gully Silt Basket (Horizontal)	2	3,000	6,000
	(W) 300MM x (L) 630MM (Dish Wash Areas) - CH 21			
Z Number	ACO hygienic box channel W300/270 L630/600 H100 D142 standard edge, FHD, EN1253, 1.4301	1	36,000	36,000
408061	ACO gully 218 telescopic DN110 vertical.locat.fl. FAT,1.4301,HF	1	15,000	15,000
416864	ACO mesh grating W268 L599,5 E30, mesh 25x25 bar 30x2, antislip, LC L15, 1.4301	1	8,000	8,000
416904	ACO 157MM Gully Silt Basket (Horizontal)	1	3,000	3,000
	(W) 150MM x (L) 150 MM (Floor Gully (EG Gullies Trap) - For Dinning Hall Floor Areas)			
401532	ACO gully EG150 tile W150 L150 D75 telescopic, for mesh grate vertical with FAT, 1.4301	22	11,000	242,000
5964	ACO mesh grate W142 L142 E20, MW 25x25,bar 20x2,electropolished antislip, 1.4301	22	5,000	110,000
			Total (Rs.)	**2,718,000**

IMP Note : -

1) All the telescopic Gully Consider below the Channel for Gr Floor & 1st Floor with Horizontal Outlet DN 110

2) For the Food Preparation ,Rice Cooker &Post Wash Consider 218 Telescopic Gully

3) Qty to be Review and Installation Height of the Channel will be Submitted after the Confirmation of BOQ

Terms and Conditions :

1) Transportation will be extra at actual

2) Delivery : 12 - 13 week from the date of Purchase Order, drawing approval & advance payment.

3) Taxes Supply: GST extra @18%

4) Validity : 30 Days from Date of Quotation

5) Installation is in your scope. Our Techncian will only guide the installation on site.

6) Unloading of Material at site is in client Scope.

7) Payment Term :- 15 days immediate after receipt of material.

Please feel free to Contact **Mr. Ravindra Kharat** on **7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd