NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

KIRPEKAR ENGINEERING PRIVATE LIMITED
Plant 1, Plo No-8A Raisoni Industrial Park
Hinjewadi MIDC , Phase-2 A/P - Maan , Tal-Mulshi , Pune-411057

Project, Location : Chakan

Date : 16.07.2021
Quote NO : SQT.21.22.0032 R1
Kind Attn : Mr. Balaji Biradar
Email Id : purchase@kirpekarengg.com
Contact No: 7774011301 / +91 9028874633

Subject : Quotation for Machine Protection Door -RP300

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Albany Make Machine Protection Door_RP 300**	1000	1200	4	690,000	2,760,000	20,000	80,000
	Total			**4**		**2,760,000**		**80,000**
	Total Without Taxe (Supply + Installations)					**2,840,000**		
2	P&F Charges			3%		**NIL**		
3	GST Extra @ 18%			18%		511,200		
	Total With Taxes					**3,351,200**		
4	Transportation Charges					**Extra at atcual**		
5	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

A	Albany Rapid Rollup Door RP300 (100% Imported with all components – made in Germany)
Construction:	Curtain RollTexPlus (silicone-free) which is specially designed for Robotics welding application without vision window, according to the following RAL colours: blue (RAL 5002)
Side frames:	Aluminum anodized two parts, to have easy access to switches and service.
Drive Unit:	Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)
Control system:	Controls MCC, IP 55 for opening / closing speed approx. 1,0 m/s. Control box with Up-Stop-Down buttons.
Power supply:	3/(N)/PE/230/400/415 V, 50 Hz.
Safety features:	Safety edge with cable chain integrated in side frames
Safety limit switch:	1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification /Information in this Concern.

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd