AMOGH DEVELOPERSS

Adding prosperity

CONSTRUCTION | REAL ESTATE

WORK ORDER

	Date : 25-02-2022
From	**To**
AMOGH DEVELOPERS	**M/s. MMC DOORTECH SERVICES (P) LTD**
PO NO:AD/AM/T Nagar 20-21/WO/09	No.22, 6TH Cross Street Trustpuram, Kodambakkam
GST NO : 33ABNFA8799A1Z6	CHENNAI-600024
	GSTIN: 33AADCM2836Q1Z5

We Are Here With Please To Issue The Work Order For The Following Works Discussed

A) Commercial Offer

Sr No	Description	Size (mm)	Qty	Supply and Installation Charges in INR	
			(Nos)	Unit Price	Total Amount
1	**Retractable Roof with PC + Structural requirement**	• ***4000 X 5600 X 800 X 4 Panel*** • ***Installation Inclusive*** • ***Inclusive Of structural work*** • ***Centre Opening***	1	9,50,000	9,50,000
2	GST Extra @ 18%		18%	**Extra At Actual**	
3	P&F Charges 3%		3%	**Extra At Actual**	
4	Transportation Charges			**Extra At Actual**	
5	Unloading Charges @ Site			**In Client Scope**	

B) Technical Specification

1. **Polycarbonate Compact Clear/Embossed 3.0 mm Thick**
2. **Profile : Powder Coated AL Frame**
3. **Guide : Annodized AL Guide**
4. **Interlocking**
5. **Dual Motor Mechanism**
   a) **2 Remote Controlled**
   b) **Single Phase Bi-directional Motor**
   c) **Speed- 09-12m/min**
   d) **Power- As per Roof Dimension**
   e) **Mechanical Limit Switch**
   f) **Rack and Pinion Arrangement -Z16/Molude4/Module6**
   g) **Italian/German Make**
6. **Control Panel**
7. **SS Fastners**
8. **EPDM Gaskets and sealantsPoly Sheet-UV Protected both sides**

AMOGH DEVELOPERSS

Adding prosperity

CONSTRUCTION | REAL ESTATE

C)	General Conditions
1	Continuous uninterrupted access to installation section or as agreed seperately.
2	Provision of 230 V power supply for hand tools.
3	A dry and secure area, not in direct sunlight is to be provided for storage of product component
4	Access to site between 7 am to 8 pm should be provided.
5	Any storage costs for material due to delay outside of NIHVA, will be in client scope.
6	The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practice. We reserve the right to extend the period accordingly.
7	Installation will start after receiving of Site Readiness Photographs or written Email communication.
8	We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.
9	For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
10	If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.
11	After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an adiitional cost.

Note:Please find below List which are in Client Scope

S.NO		Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All Bracket support/ Structural / Civil changes	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D)	Terms & Conditions	
	Price :	Ex Works Pune.
	Delivery :	6-8 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.
	Payment :	50% Advance along with Confirmed Purchase Order. 45% Along with Approval of Drawing and before start a Production. 5% Against completion of Installation, Testing and Commissioning.
	Validity :	Validity of Offer is 15 days from the date of quotation.
	Warranty :	12 months from the date of supply. It only covers damage caused due to mechanical system not due to natural calamity.

Thanking You

AMOGH DEVELOPERS

Partner