# Sales Quote

**An ISO 9001:2008 Certified Company**

**Quote No: SQT.18-19.1824** **Date: 07/17/2019**

**Shapoorji Pallonji & Company Pvt Ltd**

SP Infocity, Incubator No. 4, Pune - Saswad Road,
Phursungi,
Pune - 412308
Maharashtra -India

Kind Attention: Mr. Suresh Ashtekar

Phone:+91-8830751630-
Email ID: suresh.ashtekar@shapoorji.com

**Project Name And Location : Hospital Project at Chhindwara (MP)**

**Subject :** Quote for - Single Leaf Hermetically Sliding Door

Dear Sir,

Thank you for your opportunity and trust shown on “NIHVA.” your preferred partner for innovative solutions.This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

**Commercial Offer :-**

| Sl.No. | Description | Price | Qty | Unit | Total |
|---|---|---|---|---|---|
| 1. | Hermetically Sealed Door<br>Size : (W) 1500 mm x (H) 2400 mm x 80 mm Thick<br><br>Technical Specifications :<br>Single Leaf Automatic Sliding Door with<br>80 mm Thickness (Density 42kg/m3)<br>with 0.6mm PPGI Finish<br>• PPGI Wall Frame<br>• Heavy duty Aluminium Track<br>• Aluminium Door Profile, SS 304<br>Door Opener & Closure,<br>• FDA Approved Gasket,<br>Cladding ,Canopy ,<br>• SS 304 Integrated Pad Lock arrangement<br><br>(Supply +Installation ) | ₹ 370,000.00 | 1 | Nos | ₹ 370,000.00 |

| | |
|---|---|
| Sub Total | ₹ 370,000.00 |
| **Grand Total** | **₹ 370,000.00** |

| | |
|---|---|
| GST Pune | 27AAECN0437H1ZM |

# Sales Quote

**An ISO 9001:2008 Certified Company**

**Quote No: SQT.18-19.1824** **Date: 07/17/2019**

**General Pre requisite at site**

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required
5 Scaffolding require for Installation it is in client scope

**Limit of Supply**

1 Provide place to store the material to be installed
2 Be responsible for the safe custody of all material
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers

**Quote/Supply is based on**

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3 Billing will be as per the supply of material ,not as per site measurements

**The supply included only those mentioned in the quote & does not include**

1 Unloading from truck placement on site
2 Electrical connection for control panel

**Client Scope**

1 Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Existing/Repair/ Modification/ Refurbishment charges will be extra

**Terms & Conditions**

1 **Price** : Ex works Pune
2 **P & F Charges**: @3% of Total Supply Value
3 **Freight Notes**: Extra as applicable
4 **Payment**: 80% Advance along with confirm purchase order & Balance 20% before dispatch
5 **Taxes**: GST @ 18%
6 **Validity**: Validity of Offer is 15 days from the date of quotation.
7 **Warranty**: 12 months from the date of supply
8 **Delivery** : 4-5 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
9 **Insurance :**Extra As applicable

Please feel free to Contact **Mr. Bhavin Jain on (855) 109-2333** for any further Clarification /Information in this Concern.

With Best Regards

Smita Khare
+91-9637991333
For Nihva Technologies Pvt Ltd