NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Spunweb Nonwoven Pvt Ltd
Survery no.109(2),N.H.-27,Bamanbor-Morbi Hwy,
Near wankaner boundrary, Rangpar, Gujarat 363520

Date : 30.09.2020
Quote NO : SQT20-21.2724
Kind Attn : Jay Kagathara
Email Id : jay@spunweb.in
Contact No: **9537320032**

Subject : Quotation for NIHVA make Hydraulic Dock Leveller and ASSA Abloy Crawford Make Dock Leveller

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Make Dock Leveller 6 Ton**	2000	2500	3	200,000	600,000	20,000	60,000
2	**Assa Abloy-Crawford make Dock Leveller - 6 Ton**	2000	2500	3	395,000	1,185,000	20,000	60,000
				Total		**1,785,000**		**120,000**
	P&F Charges			3%		**53,550**		
	Total Without Taxes					**1,838,550**		**120,000**
	GST Extra @ 18%			18%		330,939		21,600
	Total With Taxes					**2,169,489**		**141,600**
	Total Supply + Installation With Taxes							**2,169,489**
2	Transportation Charges					**Extra at Actual**		
3	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) **Technical Specification**

NIHVA Make Dock Leveller






Sr. No.	Description	Specifications
1	Capacity	6 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 600 / (-) 300 mm
7	Platform Size (W x L)	2000 mm x 2500 mm
8	Lip size (W x L)	2000 x 400 mm
9	Shut Height	480 mm
10	Maximum slope can be achieved	10%
11	Clear Pit dimensions (W x L x D)	(W) 2050mm x (L)2500 mm x (D)480 mm
12	Hydraulic power pack	Standard
13	Driver type	Direct by electric Motor
14	Motor Ratings	1 H.P
15	Pump design flow	2.5 LPM
16	Pump pressure	120 bar Operating 200 bar Max.
17	Safety valve set pressure	120 Kg/cm²
18	Pump Type	Gear
19	Volume of oil receiver	7 Lit
20	No Of Deck cylinder	2 No
21	Lip Cylinder	1 No
22	Pair of Dock Bumper	Included

ASSA Abloy - Crawford make Dock Leveller





Sr. No.	Description	Specifications
1	Capacity	6 Ton
2	Platform Size (W x L)	2000 mm x 2500 mm
3	Travel above & below dock level	(+) 520 / (-) 350 mm
4	Lip size (W x L)	2000 x 400 mm
5	Control Unit Protection Class	IP 54
6	Magnetic Valves	24 V/ DC 18 W S1
7	Nominal Voltage	400 V, 3 Phase
8	Nominal Motor Power	1 HP
9	European Standard	EN 1398

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom,
Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery
: **For NIHVA make Dock Leveller** : 7 to 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
: **For ASSA Abloy- Crawford make Dock Leveller** : Minimum 12-14 weeks after receipt of confirmed Purchase order, Advance Payment and drawing approval

Payment : 80% Advance and Balance before dispatch

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mrs Sneha Bharane on 8551035333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd